

## Author's response

**Interactive comment on “Contribution of future wide swath altimetry missions to ocean analysis and forecasting” by Antonio Bonaduce et al.**

### Anonymous Referee #1

Received and published: 9 July 2018

#### *General comments*

*There are currently 3 nadir altimeters in orbit, which provide along track measurements of Sea-Surface Height (SSH). However, due to their narrow band nature, and the repeat times, the gaps between tracks are large compared to the ocean mesoscale – thus only limited spatial and temporal coverage is available. Wide swath altimeters are being developed to which would provide much greater SSH data.*

*This paper looks at the implication of such data being available to constrain model solutions for the IBI region. They note that similar studies are needed for the global scale, and for other regions.*

*They run a series of Observations Synthetic Simulation Experiments to assess the impact of assimilating the current constellation of altimeters, and future wide band altimeters. I found the experimental design satisfying, and analysis convincing.*

We thank the Reviewer for the positive comments. Here follows a point-by-point list of response for each specific comment (*highlighted in bold+italic*), as well as a marked-up manuscript version with tracked changes.

#### *Specific comments*

*I found the paper well thought out, clear and useful, and would recommend it for publication with corrections. I think it had scientific significance, scientific quality.*

Thanks.

*The presentation quality is also quite good, although I think it needs to be proof read by another native-English speaker, as there are sections that are incorrect or unclear.*

We thank the Reviewer for this suggestion. A native-English speaker (professional) proofreader revised the manuscript. The text has changed in several parts. All the changes can be noticed in the marked-up manuscript version with tracked changes.

*I think they need to reproduce the graphics with a better colour-map – jet/rainbow is very misleading.*

We thank the Reviewer for this comment. The maps are shown now with a perceptually proportional palette.

*I thought there should be a bit more description of the altimeters and of the ocean forecasting/analysis/reanalysis system.*

We thank the reviewer for this comment. A table (Table 2) was added, showing the characteristics of the altimetry missions considered in this study and the text has changed to describe more the ocean analysis and forecasting system considered in this study (Page 3: lines 31-35).

***I think there could be a little more discussion of what the statistics mean physically, in terms of location, mechanism etc.***

We thank the Reviewer for the appropriate comment. The text has changed discussing more about the physical meaning of the impacts observed (Page 9: lines 25-27; Page 10: lines 6-9; Page 10: lines 24-25).

***I have outlined these specific comments here.***

***Page 4: End of introduction. Later in the paper when you start talking about forecast errors, I realised that it was not a reanalysis study – I wonder if this should be further clarified in the introduction . . . perhaps a sentence of two describing the forecast/analysis system, something like: . . . data is assimilated in 2 day analysis part of the run, which then is run freely as a 5 day forecast, with the end of the analysis used as initial conditions for the next forecast cycle. We use the analysis period to assess the impact of ssh, and then compare the errors in the 1st, 3rd and 5th day of the forecast period). . .***

We thank the Reviewer for the appropriate comment. The text in the Introduction has changed (Page 3: lines 31-35):

“The system used in this study differs from operational systems, in the sense that the same atmospheric forcings are used both in the hindcast and forecast. First, the system is run freely as a 5-day forecast to compute innovations (difference between observations and model background). Then, data is assimilated in a 5-day analysis, with the end of the analysis used as initial conditions for the next forecast cycle. Both analyses and forecastings fields are stored to assess the impact of altimetry data in ocean analyses and forecasting skill (no data-assimilation, same atmospheric forcings) in the 1st, 3rd and 5th day of the forecast period.”

***Page 7: section 2.3.2. Need to give more information on the current Nadir altimeters: how often do they pass over a particular place? How wide is the footprint? How wide is it between passes (compare to the newer ones)? What does 1Hz mean in terms of km’s? You say the wide swath altimeters have 20.9 day repeats, and 7km – does this imply that the same is true for the nadir satellites? Perhaps a table giving these details might be useful.***

We thank the Reviewer for this comment. We added a Table describing the characteristics of the satellite altimetry missions considered (Table 2). The text has also changed in the manuscript:

- page 7: lines 7-9. “Conventional altimetry data were derived from sampling the NR over the theoretical tracks of the satellite missions Jason 2, Cryosat 2 and Sentinel 3a, with a sampling frequency of 1 Hz (~7 km spatial sampling; e.g. Roblou et al. 2011).”

- page 7: lines 15-16: “The specifics for each satellite altimetry mission considered in this study are detailed in Table 2.”

***Page 7: section 3. Did you consider an OSSE assimilating TS and SST, but not SSH? Assuming correcting the ocean temperature structure won’t affect the SSH through expansion, but it may constrain eddies, which would affect the SSH?***

We thank the Reviewer for this comment. The Reviewer is right, ocean temperature structure can constrain eddies and as a consequence can affect the SSH. On the other hand, in literature it is known that satellite altimetry observations has a major impact, with respect to the other observations systems,

to constrain the ocean variability due to mesoscale structures (Lea et al., 2014, Oke et al., 2015, Verrier et al., 2017) and nowadays they are assimilated in realistic ocean analyses and forecasting systems (Le Traon et al., 2015). The OSSEs performed in this study were designed in order to be representative of the evolution of errors found in real ocean analysis and forecasting systems. The system used here (IBI) is adopted by CMEMS to provide operational analyses, forecasts and ocean reanalysis where all the best quality flagged observations (e.g. SSH, TS, SST) are ingested by system. In order to perform realistic OSSEs, we decided on purpose to assimilate TS, SST and SSH in all the OSSEs, and to quantify the impact of wide-swath altimeters looking at the variations of the error due to the different SSH synthetic observations considered. We adopted this approach to achieve the objective of the study, which was to assess the impact of future constellations with respect to the current altimeters. For these reasons in this study we didn't consider an OSSE assimilating only TS and SST.

## References

Le Traon, P. Y., Antoine, D., Bentamy, A., Bonekamp, H., Breivik, L., Chapron, B., Corlett, G., Dibarbouré, G., DiGiacomo, P., Donlon, C., Faugère, Y., Font, J., Girard-Ardhuin, F., Gohin, F., Johannessen, J., Kamachi, M., Lagerloef, G., Lambin, J., Larnicol, G., Borgne, P. L., Leuliette, E., Lindstrom, E., Martin, M., Maturi, E., Miller, L., Mingsen, L., Morrow, R., Reul, N., Rio, M., Roquet, H., Santoleri, R., and Wilkin, J.: *Use of satellite observations for operational oceanography: recent achievements and future prospects*, *Journal of Operational Oceanography*, 8, s12–s27, <https://doi.org/10.1080/1755876X.2015.1022050>, 2015.

Lea, D. J., Martin, M. J., and Oke, P. R.: *Demonstrating the complementarity of observations in an operational ocean forecasting system*, *Q. J. R. Meteorol. Soc.*, 140, 2037–2049, <https://doi.org/10.1002/qj.2281>, 2014.

Oke, P., Larnicol, G., Jones, E., Kourafalou, V., Sperrevik, A., Carse, F., Tanajura, C., Mourre, B., Tonani, M., Brassington, G., Henaff, M. L., Jr., G. H., Atlas, R., Moore, A., Edwards, C., Martin, M., Sellar, A., Alvarez, A., Mey, P. D., and Iskandarani, M.: *Assessing the impact of observations on ocean forecasts and reanalyses: Part 2, Regional applications*, *Journal of Operational Oceanography*, 8, s63–s79, 2015. <https://doi.org/10.1080/1755876X.2015.1022080>.

Verrier, S., Le Traon, P.-Y., and Remy, E.: *Assessing the impact of multiple altimeter missions and Argo in a global eddy-permitting data assimilation system*, *Ocean Science*, 13, 1077–1092, <https://doi.org/10.5194/os-13-1077-2017>, <https://www.ocean-sci.net/13/1077/2017/>, 2017.

**Page 8: Line 26. Clarify exactly what variance you mean. I assume you mean a spatial map of temporal variance. Maybe add an equation along the lines of ...:**

Thanks for this comment. The reviewer is right, here we mean maps of temporal variance. The equation was added (Page 9: lines 4-5). The text has also changed (Page 9 : lines 2-3) :

“In particular VarError and Var (NR) are spatial maps of temporal variance, which (considering SSH data), are defined as ...”

**Page 9: Line 31-32. It is good to see you talk about what the improved statistics mean physically (in terms of ocean features). You should do more of this in the paper.**

We thank the Reviewer for this comment. The text has changed and further discussion about the physical meaning of the improved statistics is given at:

- Page 9: lines 25-27. “Large errors were observed in occurrence of the main features of the ocean circulation in the IBI region, both in the northern (e.g. North Atlantic Drift) and southern part of the domain (e. g. Azores Current), as well as in the Bay of Biscay.”

- Page 10: lines 6-9. The impact of wide-swath altimetry measurements can be noticed over the entire spatial domain and in particular in the areas of the ocean characterized by the signature of the North Atlantic, Azores and Canary Currents and in the occurrence of mesoscale eddies in the Bay of Biscay, where large errors were observed considering only nadir altimeters.”

- Page 10: lines 24-25. “This involve a further improvement of the representation of the ocean dynamics due to the main ocean currents and mesoscale structures which characterize the SSH variability in the IBI region.”

**Page 20: Figure 1. I suggest you use a perceptually uniform colour map, and don't use the jet/rainbow style colour map. This applied to all the map figures.**

Thanks for this appropriate comment. Map figures are shown using a perceptually uniform colour map, except those showing the synthetic observations (Figure 1 and 2) to differ from map figures which show the results of this study (Figure 3, 6 and 7).

#### **Technical corrections**

**Page 2: Line 6. “these” and “source” need to agree – perhaps “these unique sources”.**  
Corrected.

**Page 2: Line 28. Change “could not be suitable” to “may not be suitable”?**  
Corrected.

**Page 3: Line 14. Remove the space before the semi colon “NEMO ; Madec” vs “NEMO;Madec”.**  
Corrected.

**Page 3: Line 15. Perhaps change “nature” run’ to “natural” run’?**  
Corrected.

**Page 4: Line 4. Remove “a” from “In this study a particular attention..”**  
Corrected (Page 4: line 8).

**Page 4: line 25. You say the “last version”. Do you really mean Last, latest or previous?**  
Thank for this comment. We mean the “latest”: the text has changed, referring to the “latest version” (Page 4: line 29).

**Page 4: line 26. Remove extra space, change “used , the” with “used, the”**  
Corrected (Page 4: line 30) .

**Page 6, Line 7. Remove extra space after reference.**  
Corrected (Page 6: line 11).

**Page 6: line 29. Should it be daily average sst? I guess it depends on the assimilation system?**

Thanks for this comment. It depends on the assimilation system used. The text has changed (Page 6 : lines 31-32; Page 7: line 1):

“To accurately assess the impact of satellite altimetry data on ocean analyses and forecasts, the same synthetic observations of SST, T and S profiles were considered in all the experiments. An SST map representing a daily average is assimilated during each 5-day assimilation cycle.”.

**Page 8: line 4-5. Incorrect phrasing, please rephrase “As already mentioned, SWOT-like data have a temporal resolution which could not allow to resolve correctly the evolution of mesoscale structures”**

Thanks for this comment. The text has changed (Page 8: lines 9-11):

“As already mentioned, SWOT-like data has a temporal resolution which does not allow the evolution of mesoscale structures to be resolved correctly”.

**Page 8: line 8. Is order of magnitude the correct term?**

Thanks. The expression “order of magnitude” was omitted (Page 8: line 14).

**Page 8: Line 13-16. Justify the values of the improved radar interferometer error values in OSSE4. Is this a possible improvement?**

Thanks for this comment. The error values in OSSE4 represent a possible scenario analyzed by Thales Alenia Space (TAS) to develop European wide-swath altimetry concepts, with less stringent noise requirements compared to SWOT mission. The text has changed (Page 8: lines 18-23):

“In order to investigate the sensitivity of the ocean analysis and forecasting system to the error of a wide-swath altimetry instrument, a dedicated OSSE, hereafter OSSE4, was performed considering a satellite constellation as in OSSE3 but assuming a radar interferometer error of one half the order of magnitude (0.4 - 1 cm) with respect to the other OSSEs (2 x KaRIN error). The error values in OSSE4 represent one of the solutions analyzed by TAS, as part of this ESA study, to develop European wide-swath altimetry concepts. The experimental set-up used in this study is detailed in Table 2.”

**Page 8: line 15. Change ‘an halved’ to ‘a halved’**

Corrected (previous answer).

**Page 8: line 19. Do you mean NR? If so, change for consistency.**

Corrected (Page 8: line 26).

**Page 8: line 20. Perhaps helpful to say steep bathymetric slope or deep sea-bed slope might otherwise confuse some readers.**

Thanks for the comment. The text has changed (Page 8: lines 26-27): “...steep bathymetric slope separating...”.

**Page 8: line 21. Change word order to ‘was also captured’**

Corrected (Page 8: lines 28-29).

**Page 8: Line 25. Perhaps call var\* relative variance?**

Thanks. The text has changed (Page 9: line 2): “...we considered the relative variance VAR\* defined...”.

**Page 9: Line 8. Change ‘an higher’ to ‘a higher’**

Corrected (Page 9: line 19).

**Page 9: Line 17. Is 20-30**

Corrected (Page 10: Line 1).

**Page 9: Line 26. Is the 6**

Thanks. The text has changed (Page 10: line 16): “V AR\* was also 6% lower for OSSE2 than for OSSE1.”

**Page 10: Line 3. Add a reference to Table 4.**

Corrected referring to Table 5 (Page 10: line 26).

**Page 10: Line 10. Is this the correct table?**

Thanks for the comment. The reference to Table was correct, but the text was misleading. The text has changed (Page 10: line 34): “The results of the impact of wide-swath altimetry data on the SSH in ocean analysis are summarized in Table 4.”.

**Page 10: Line 15. Is 19W too close to your lateral open boundary?**

The reviewer is right, 19W can be considered close to the lateral open boundary. The sub-domain was selected in order to consider an open ocean region characterized by high mesoscale activity in the IBI domain. This was a compromise between the extension of the area considered (which affect the spatial scales in a spectral analysis), and the distance from the lateral boundary.

**Page 10: Line 21-23. The wording is confusing in this sentence, feels like it's the wrong way around.**

Thanks for this comment. The text has changed (Page 11: lines 11-13): ”Here the reduction of the error at the different wavelength (ERspec) is defined as the percentage decrease of the error with respect to OSSE0 (Table 6), in order to asses also the impact of nadir altimeters”.

**Page 10: Line 21. Change word order ‘to evaluate also’ to ‘to also evaluate’.**

Corrected (previous answer).

**Page 10: Line 24. Looks like you can see the impact to 50km, although to a much smaller level. Perhaps add a qualifier here, or weaken.**

Thanks for this comment. The text has changed (Page 11: lines 14-15): “Considering nadir altimeters (blue curve), the impact on ocean analysis is noticeable at spatial scales down to 100 km, while is weaken at wavelengths of 50 km.”

**Page 10: Line 27. Also add a reference to table 7 – something like “(Figure 7, left panel; Table 7)”.**

Corrected (Page 11: line 17).

**Page 10: Line 30-32. What about the difference between OSSE2 and OSSE3? I assume you mean it's interesting to notice that the difference is small, but maybe no. . .clarify.**

Thanks for this appropriate comment. The text has changed (Page 11: lines 20-23): “Here it is also interesting to note that the difference between OSSE2 and OSSE3 (purple and red lines) is small, while is significant comparing OSSE2 and OSSE4 (green line) showing the impact of the higher repeat cycle of the SSH measurements and the sensitivity of system to the error of a wide-swath instrument.

**Page 11: Line 17. Change word order “increased significantly” to “significantly increased”.**

Corrected (Page 12: line 7).

**Page 12: Line 2. We’ve just been talking about Table 5, do you need this last sentence?**

Thanks for this comment. The sentence was omitted.

**Page 13: Line 5. Do you mean OSSE4 when you say “accurate” if so, clarify. Also applied to Line 27**

Thanks for this comment. The text has changed (Page 13: line 26; Page 14: lines 2-3 and 17) referring explicitly to OSSE4.

**Page 13: Line 22. Change word order from “observed also” to “also observed”.**

Corrected (Page 14: line 11).

## Figures

**Page 21: Line 3. Use left, centre, right to describe the upper panels. It is unclear using semi-colons.**

Corrected. The text in the caption of Figure 2 has changed: “Top panels: satellite altimetry spatial coverage during one assimilation cycle (5 days); left: Jason2, Cryosat 2 and Sentinel 3a; central: Swath-1; right: Swath-1 & Swath-2.”

**Page 22: Figure 4. Given the whitespace in the upper left, perhaps add OSSE1 in blue. . . OSSE4 in green text. This applies to figure 5 and 7. It’s good you’ve used the same colour ordering for these panels. Check the colour for colour blindness. Perhaps removed the 100’s of x ticks.**

Thanks. Figure 4, 5 and 7 have changed showing the experiments legend. In the Figures, the legend has changed to take into account color blindness (e.g. <https://rdrr.io/cran/ggthemes/man/colorblind.html>):

- OSSE1 (blue; RGB: #56B4E9) ;
- OSSE2 (orange; RGB: #E69F00) ;
- OSSE3 (purple; RGB: #CC79A7) ;
- OSSE4 (green; RGB: #009E73).

The 100's of x ticks were removed in Figure 4.

**Page 22: Line 3 (caption for Figure 4). Change “(blue lines)” to “(blue line)”.**

Corrected.

**Page 23: Line 2. Type – Frebruary – change to February**

Corrected (caption for Figure 5).

**Page 25: Figure 7. Break Y axis on the left hand panel, (i.e. y values of 0-4 and then 4-10) to capture the top of the grey line.**

Thanks. Left panel in Figure 7 has changed accordingly.

**Page 25: Line 2-3. Confusing text. . . perhaps say something like “. . . February-December 2009. The results for experiments OSSE0. . . OSSE4 (green lines) are shown at the spectral window between 400km and 12km.”**

Thanks for this comment. The caption of Figure 7 has changed accordingly.

## ***Tables***

***Page 29. Table 5. Add km to the last 3 columns (280km, 155km, 125km. . .)***  
Corrected (Table 6).

***Page 29: Table 6. Add columns for current magnitude.***  
Corrected (Columns 1-3 and in Table 7).

## Author's response

**Interactive comment on “Contribution of future wide swath altimetry missions to ocean analysis and forecasting” by Antonio Bonaduce et al.**

**Anonymous Referee #2**

Received and published: 21 August 2018

*This paper evaluates the impact of assimilating wide-swath altimetry to improve ocean analysis and prediction. Observing System Simulation Experiment (OSSE) methodology is used in a regional setting in the northeastern Atlantic Ocean to evaluate the impact of this future observing technology in comparison to the impact of existing along-track altimetry. Errors in ocean analyses are further reduced by up to 50% over the reduction achieved by assimilating the existing constellation of along-track altimeters. Substantial error reduction is maintained by short-term ocean forecasts initialized by these data-assimilative ocean analyses.*

*This is a significant paper for two reasons. First, the authors followed rigorous procedures with respect to the design and validation of the OSSE system to ensure that credible impact assessments are obtained. Second, wide-swath altimetry is an important new technology that holds the promise of significantly improving the analysis and prediction of ocean mesoscale variability. The experimental design is reasonable. This paper provides an important early quantitative assessment of the expected improvement when wide-swath altimetry becomes operational.*

*The paper is clearly written and I have no significant editorial recommendations.*

*For these reasons, I recommend publication as is.*

We thank the Reviewer for the positive comments (*highlighted in bold+italic*) and for considering this paper as a significant study.

# Contribution of future wide swath altimetry missions to ocean analysis and forecasting

Antonio Bonaduce <sup>1,\*</sup>, Mounir Benkiran <sup>1</sup>, Elisabeth Remy <sup>1</sup>, Pierre Yves Le Traon <sup>1,2</sup>, and Gilles Garric <sup>1</sup>

<sup>1</sup>Mercator Ocean, Toulouse, France

<sup>2</sup>Ifremer, Plouzané, France

\*now at: Helmholtz-Zentrum Geesthacht Centre for Materials and Coastal Research, Geesthacht, Germany

*Correspondence to:* A. Bonaduce (antonio.bonaduce@hzg.de)

**Abstract.** The impact of forthcoming wide-swath altimetry missions on the ocean analysis and forecasting system was investigated by means of OSSEs (Observing System Simulation Experiments) performed with a regional data assimilation system, implemented in the Iberian-Biscay-Ireland (IBI) region, at 1/12° resolution using simulated observations derived from a fully eddy-resolving free simulations at 1/36° resolution over the same region. The objective was to ~~asses~~assess the contribution of different satellite constellations to constrain the ocean analyses and forecasts, considering both along-track altimeters and future wide-swath missions, and ~~as consequence~~consequently the capability of the data assimilation techniques used in the Mercator Ocean operational system to effectively combine the different ~~kind~~kinds of measurements. This was carried out as part of a European Space Agency (ESA) study on the potential role of wide-swath altimetry ~~for the evolution in future~~versions of the European Union Copernicus programme. The impact of future wide-swath altimetry data is ~~clearly~~evident investigating the reliability of sea-level in ~~the~~OSSEs. The most significant results were obtained looking at the sensitivity of the system to wide-swath instrumental error: considering a constellation of three nadir and two "accurate" (small instrumental error) wide-swath altimeters, the error in ~~the~~ocean analysis was reduced ~~up to the~~by up to 50 %, ~~with respect~~when compared to conventional altimeters. Investigating the impact of the repetitivity of the future measurements, the results showed that two wide-swath missions had a major impact on ~~the the~~sea-level forecasting increasing the accuracy over the entire time-window of the 5-day forecasts, with respect to a single wide-swath instrument. A spectral analysis underlined that the contributions of wide-swath altimetry data observed in ~~the~~ocean analyses and forecasts statistics were mainly due to ~~resolve more accurately~~(up to > 25 %), with respect ~~the more accurate resolution, compared with~~to along-track data, ~~the of~~ocean variability at spatial scales smaller than 100 km. Considering the ocean currents, the results confirmed that the information provided by wide-swath measurements at the surface is propagated ~~also in the vertical to~~water column and has a considerable impact (30 %) on ~~the~~ocean currents (up to a depth of 300 metres), ~~with respect~~compared to the present constellation of altimeters. The ocean analysis and forecasting systems used here are ~~currently adopted by those currently used by the~~Copernicus Marine Environment and Monitoring Service (CMEMS) to provide operational services and ocean re-analysis. The results obtained in the OSSEs considering along-track altimeters were consistent with those derived ~~with from~~real data (observing system experiments, OSEs). OSSEs ~~also allow to evaluate~~can also be used to assess the potential of new observing systems, and in

this study the results showed that future constellations of altimeters will have a major impact ~~to constrain~~ for constraining the CMEMS ocean analysis and forecasting systems and their applications.

*Copyright statement.* TEXT

## 1 Introduction

5 Satellite altimetry measurements, based on nadir radar altimeters, have ~~been made~~ a fundamental contribution to the understanding of ~~the~~ ocean circulation (Fu and Chelton, 2001; Le Traon and Morrow, 2001) ~~;~~ during the past two decades. The continuous improvement of the physics aspects in the Ocean General Circulation Models (OGCMs) and of data assimilation schemes (DAS) (Bell et al., 2015), ~~nowadays allow exploiting these unique source of information within now~~ make it possible to exploit these unique sources of information in global and regional ocean monitoring and forecasting systems (Le Traon et al.,  
10 2017b). The focus of the present study is to investigate the impact of wide-swath altimetry on a ~~high resolution~~ high-resolution regional ocean analysis and forecasting system. This is carried out as part of a European Space Agency (ESA) study on the potential role of wide-swath altimetry for the ~~evolution~~ further development of the European Union Copernicus programme (space component).

While along-track measurements can observe wavelengths up to 50-70 km (Dufau et al., 2016), the representation of ~~the~~ ocean mesoscale dynamics is strongly limited by the spatial (distance between ~~neighboring~~ neighbouring tracks) and temporal (repeat period) sampling of a given altimeter mission. ~~The use of multiple altimeters is needed~~ It is necessary to use multiple altimeters to constrain the mesoscale circulation (Le Traon et al., 2015) and to provide global maps of the mesoscale variability of the ocean (Le Traon and Dibarboure, 1999; Morrow and Le Traon, 2012). In the literature, the works that focus on the capability of altimeter constellations to resolve ~~the~~ ocean dynamics at ~~the~~ mesoscale resolution (e.g. Dufau et al., 2016),  
20 ~~highlighted~~ concluded that at least three altimeters are required to reconstruct sea-level variations (Pascual et al., 2006; Dibarboure et al., 2011) and that the merging of multiple altimeter missions cannot resolve wavelengths smaller than 150 - 200 km (Ducet et al., 2000; Le Traon, 2013). The shortcomings of ~~the~~ conventional altimetry could be addressed by wide-swath measurements of ~~the~~ sea-surface height (SSH) planned for ~~the~~ future space missions (e.g. the Surface ~~Ocean and Water~~ Water and Ocean Topography, SWOT, Mission; Fu et al., 2009; Durand et al., 2010), extending the capability of existing nadir altimeters  
25 to two-dimensional mapping and sampling the ocean surface at unprecedented spatial resolution resolution, up to wavelengths of 20 km (Fu and Ferrari, 2008).

The forthcoming altimeter missions based on radar interferometry to obtain wide-swath measurement of sea-surface elevation (Fu et al., 2009), ~~represent the next generation~~ will involve next-generation satellite altimetry measurements with a high potential for ocean analysis and forecasting. The NASA/CNES SWOT mission will be the first ~~swath~~ wide-swath altimetry  
30 mission to be launched in 2021.

Wide-swath altimetry concept is expected to ~~represent~~ make an essential contribution to operational oceanography (Bell et al., 2015; Le Traon et al., 2017b). On the other hand, the temporal resolution of wide-swath data, considering SWOT-like orbit parameters (repeat cycle of 21 days with a ~~10-days-10-day~~ subcycle), ~~could~~ may be not suitable ~~to resolve~~ for resolving the evolution of mesoscale eddies (Ubelmann et al., 2015). A major challenge will be to combine data from ~~both~~ wide-swath and the conventional along-track altimeters (Pujol et al., 2012) ~~data~~ with high resolution OGCMs to ~~allow~~ a dynamical ~~enable a dynamic~~ interpolation of wide-swath data and a detailed description and forecast of the ocean state at high resolution. Approaching the challenge of using wide-swath altimetry data to reconstruct oceanic fields, Gaultier et al. (2016b) underline the need ~~of testing~~ to test their effective impact on ~~the~~ ocean analyses and forecasts by performing observing system simulation experiments (OSSEs). This ~~work represent a first effort~~ study is a first attempt to investigate the impact of forthcoming wide-swath altimetry data in an ocean analysis and forecasting system by means of OSSEs.

Observing ~~sytem~~ system experiments (OSEs; e.g. Oke and Schiller, 2007) and OSSEs (e.g. Halliwell et al., 2017) are rigorous methods ~~to provide demonstrations of~~ for demonstrating the impacts of observations (Schiller et al., 2015) on global (Oke et al., 2015a) and regional (Oke et al., 2015b) ocean forecasting systems, as underlined by the GODAE OceanView International Programme (Bell et al., 2015). OSEs analyse the impact of real observations through data denial experiments, where the impact is determined by the increase in analysis and forecast errors due to neglecting a given observing system (Atlas et al., 2015). OSSEs extend this procedure to the ~~evaluation~~ assessment of new deployment strategies and sampling characteristics for existing systems, and to the design of new observing systems. Observations are, in the case of OSSE, simulated to mimic the sample and error specification of the future network design and then assimilated.

As described in the literature (e.g. Errico et al., 2013), OSSEs typically use two different OGCMs or two different OGCM configurations. Halliwell et al. (2014) proposed a "fraternal twin" approach, where the same OGCM was used for both the observation simulation and the assimilative model, to ~~evaluate~~ assess the impact of Earth observations (EO) in the ocean. This approach was ~~adopted also~~ also adopted in this study, using two different configurations of the Nucleus for European Modelling of the Ocean (NEMO; Madec, 2016). A first configuration is used to perform a "~~nature~~ natural" run (hereafter NR) to represent the "true" ocean. Synthetic observations are obtained by sampling the NR in order to mimic either an existing or future observing system. ~~The synthetic observations are then ingested, through~~ Using data assimilation techniques, ~~in the~~ synthetic observations are then fed into numerical simulations performed with a second OGCM configuration, to obtain a representation of the state of the ocean constrained by the observing system considered (assimilated run). The impact of the simulated observation system is quantified by comparing the assimilated run (AR) ~~against with~~ the NR and the different performances among the OSSEs can be ~~evaluated~~ assessed by the reduction (increase) of ocean analysis and forecast errors due to considering (neglecting) the new observing ~~systems designed~~ system designs.

OSSEs are complementary to OSEs and the results for existing observing systems must be consistent with those derived from OSSEs. In particular, the ~~growth~~ increase (reduction) of the error ~~among~~ between the NR and the assimilated run in the OSSEs should have an order of magnitude comparable to ~~the one that~~ obtained in the OSEs comparing a realistic ocean analysis and forecasting system, which ~~consider~~ considers real observations, with the real ocean. The calibration of OSSEs with respect to OSEs is ~~an important element to obtain~~ important for obtaining robust results from OSSEs (Halliwell et al., 2014,

2017; Kourafalou et al., 2016). In this sense, the choice of the NR, ~~assimilated-run (AR)~~AR, data assimilation scheme (DAS) and the errors to be considered for the synthetic observations have to be carefully analysed to avoid ~~inconsistent departures of unrealistic~~ forecast and analysis errors in the OSSEs. In this ~~work-study~~ we investigated the potential impact of future constellations of satellite altimeters, based on nadir and wide-swath missions, using a regional ocean analysis and forecasting system implemented in the Iberian-Biscay-Ireland (IBI) region at ~~the-a~~ spatial resolution of 1/12°. The system was validated against in situ and satellite observations and ~~continues to~~ provide operational services and ocean re-analysis (Sotillo et al., 2015) within the framework of the Copernicus Marine ~~Enviroment-Environment~~ and Monitoring Service (CMEMS). The ~~system used in this study differs from operational systems in the sense that the same atmospheric forcings are used both in the hindcast and forecast. First, the system is run freely as a 5-day forecast to compute innovations (observation minus model forecast equivalent). Then, data is assimilated in a 5-day analysis, with the end of the analysis used as initial conditions for the next forecast cycle. Both analyses and forecastings fields are stored to assess the impact of altimetry data in ocean analyses and forecasting skill in the 1st, 3rd and 5th day of the forecast period.~~

The main objective of this study was to quantify the impact of assimilating wide-swath altimetry data on ~~the errors in the errors in~~ ocean analyses and forecasts.

OSSEs are also important tools for testing the capability of ~~the-a~~ DAS to effectively merge different types of observations with models to produce improved ocean analyses and forecasts. Wide-swath measurement ~~noiseerror~~, due to radar interferometer ~~instrumentnoise~~, and its cross-track variability within the swath, will also be a complex issue which must be taken into account (Hénaff et al., 2008) to ensure ~~an~~-effective use of the data. In this study~~a-~~, particular attention was ~~given-paid~~ to the sensitivity of the ocean analysis and forecasting system to ~~the-instrumental-error-of-instrumental error in~~ wide-swath altimetry measurements. The aim was to test the capability of the Mercator Ocean DAS to use and merge nadir and wide-swath altimeters, which to the best of our knowledge has never been investigated using a regional ocean analysis and forecasting ~~systemssystem~~.

The paper is organized as ~~foHow~~follows. Section 2 describes the ocean modelling and data assimilation components of ~~the~~-OSSEs, as well as the synthetic observations considered in the different experiments. The experimental set-up designed to assess the impact of wide-swath altimetry data is detailed in Section 3. The impact of wide-swath data at the surface is investigated in Section 4. The contribution of the new observing systems to the representation of ~~the~~-ocean variability at different spatial scales is ~~evaluated-discussed~~ in Section 5. Section 6 shows the impact of wide-swath altimetry data on the ~~study of~~ ocean circulation, both at the surface and in the water column. All the results are summarized in Section 7 and some conclusions are drawn.

## 2 OSSE approach

ESA is conducting a study to assess the feasibility and potential of wide-swath altimetry for the EU Copernicus programme. The main objective is to provide a much improved operational monitoring of ~~the~~-ocean mesoscale variability for the Copernicus Marine Service (e.g. Le Traon et al., 2017a). Different wide swath altimeter concepts ~~are-analyzed-were analysed~~ by Thales

Alenia Space (TAS) as part of this ESA study. Compared to the SWOT mission that is focused on submesoscale variability, these European wide-swath altimetry concepts have less stringent noise measurement requirements. Their potential for ocean analysis and forecasting are ~~analyzed~~analysed here by means of OSSEs.

In this Section we describe the OSSEs components, represented by the OGCM configurations used to obtain the synthetic observations and to perform data assimilation experiments, the DAS adopted to consider the new observing systems in ~~the~~ ocean analysis, the simulated ocean observations and their errors.

## 2.1 OGCM configurations

In this study, both ~~the~~ NR and the AR rely on the ~~last~~lastest version of the NEMO OGCM (NEMO v3.6; Madec, 2016). Following a "fraternal twin" ~~approach~~approach (Halliwell et al., 2014), even though the same OGCM type is used, the NR and the AR are configured differently so that the errors (differences between NR and AR) are similar to the ~~one~~those found between state-of-the-art ocean models (e.g. Maraldi et al., 2013; Sotillo et al., 2015) and the true ocean.

The NR is a ~~free-running~~free-running simulation of the NEMO OGCM, implemented in the IBI region at an eddy resolving spatial resolution and using an explicit free surface formulation (Madec, 2016; Oddo et al., 2014). The primitive equations are discretized on ~~an~~a horizontal curvilinear grid which is a refined subset at  $1/36^\circ$  (2-3 km) of the so-called "ORCA" tripolar grid, commonly used in other NEMO-based large-scale and global modelling experiments (Barnier et al., 2006). The water column is discretized using 50 unevenly spaced vertical  $z$  levels with partial cells to fit the bottom depth shape. A  $1/36^\circ$  horizontal resolution was chosen for the NR in order to resolve the mesoscale in the ocean ~~almost-over~~over almost the entire IBI domain (Hallberg, 2013).

An ~~eddy-resolving~~eddy-resolving OGCM configuration was also used for the AR, but at a coarser spatial resolution to resolve the mesoscale structures with a lower accuracy than the NR. In terms of spatial resolution, the difference between the two configurations is that the AR uses a  $1/12^\circ$  tripolar grid (ORCA12) and 75 vertical levels. A different spatial resolution between the NR and AR configurations was chosen to determine how assimilating high-resolution data into a coarser OGCM can ~~contribute-to~~help increase the accuracy of the representation of the "true" mesoscale dynamics (given by the NR). In order to obtain independent results and quantify the impact of assimilating synthetic satellite altimetry observations from the NR in the AR, the two configurations were initialized differently. Initial conditions in AR were obtained from a ~~7-years~~7-year model spin-up (2002 - 2008) performed as a free run, forced by atmospheric forcings but without data assimilation.

The AR is forced by ~~3-h~~3-hour,  $0.5^\circ$  horizontal-resolution atmospheric re-analyses from the European Centre for Medium-Range Weather Forecasts (ECMWF-ERA-Interim, Dee et al., 2011). Atmospheric pressure and tidal potential (Lyard et al., 2006; Egbert and Erofeeva, 2002) are included in the model forcings. Lateral open boundary and initial conditions fields (Temperature, Salinity, Velocities and Sea level) are obtained from the Mercator global ocean reanalysis (daily output) at  $1/4^\circ$  (GLORYS; Garric et al., 2018). As the atmospheric pressure forcing is not considered in the global reanalysis, the inverse barometer effects (e.g. Wunsch and Stammer, 1997) are computed from the ECMWF pressure fields and applied along the boundaries. Tidal harmonics were obtained from a 10-year free run simulation, performed using the same OGCM configuration (AR). On the other hand, NR is forced by the ~~3-h~~3-hour,  $0.25^\circ$  horizontal-resolution operational analyses from ECMWF and

Mercator global ocean analysis data are considered as initial and boundary conditions. In this configuration, tidal harmonics were obtained from the ~~last-most recent~~ version of the FES (Finite Element Solution) tide model (FES2014, Lyard et al., 2017). All the differences between the NR and AR configurations are listed in Table 1.

Starting from the same initial conditions, the OSSEs were performed from the 1st of January 2009 over ~~almost 1-year~~  
5 ~~time-period~~ a period of almost one year, assimilating synthetic observations from different satellite constellations, in-situ temperature ~~and~~ , salinity profiles and SST maps.

## 2.2 Data assimilation scheme (DAS)

The impact study designed in this work was performed using an updated version of the data assimilation scheme developed at Mercator Ocean, called SAM2 (Système d'Assimilation Mercator V2), described by Lellouche et al. (2013a). In SAM2 the  
10 background error covariance matrix is based on a fixed collection of model anomalies. The anomalies are computed from a numerical experiment and at each date they are given by the difference between the free run outputs and their temporal running mean. The aim is to obtain an ensemble of anomalies representative of the error covariances (Oke et al., 2008), which provide an estimate of the error on the ocean state at a given period of the year that is realistic with-in terms of the climatological statistics.

15 In this study, we consider a 7-year ~~free-model-run~~ model run with no data assimilation to obtain anomalies for Temperature (T), Salinity (S), zonal velocity (U), meridional velocity (V) and Sea-Surface Height (SSH). At the date of an analysis the anomalies are considered over a  $\pm 60$ -day temporal-time window and from the different years ~~,resulting in a number of~~  
~~anomalies equal to~~ ( $\sim 365$  ~~for each given analysis~~ anomalies for each analysis). These anomalies are selected according to the season of the assimilation cycle in order to get a basis evolving consistently with the model climatology. ~~Thus~~ In this way the  
20 background errors are not propagated by the ~~dynamical~~ dynamic model but evolve with ~~the time~~ time, as errors are based on anomalies ~~which-that~~ change at each analysis date. In this study, the anomalies were obtained considering 25-hour averaged fields. The ~~localization of the error covariance is performed~~ error covariance was localized assuming a zero-covariance beyond a distance defined as twice the local spatial correlation scale, which is about 80 km in the IBI region. The spatial correlation scales, estimated from IBI regional ocean re-analysis (Sotillo et al., 2015), are also used to select the data around the analysis  
25 point.

The model correction (analysis increment) is a linear combination of these anomalies and depends on the innovation (observation minus model forecast equivalent as in Ide et al., 1997) and on the specified observation errors. This correction is applied progressively over the assimilation cycle temporal window using an incremental analysis update (IAU; Bloom et al., 1996; Benkiran and Greiner, 2008) for an enhanced ~~dynamical~~ dynamic balance. In this study wide-swath altimetry data were  
30 obtained considering a  $\sim 20$ -day repeat orbit with a 10-day subcycle (Gaultier et al., 2016a). Here we selected a 5-day assimilation cycle, because it seems appropriate ~~regarding~~ concerning the half cycle of wide-swath data, and the ocean analysis was performed in the middle of the assimilation window.

A bias correction based on variational methods (3D-Var) is applied to the model's prognostic equations to correct large scale and slowly evolving errors in T and S diagnosed from the in-situ profile innovations. The model equivalents to SSH

observations ~~was~~were computed considering a 25-hour average, to filter the tidal signal. Finally, with respect to the operational systems (Lellouche et al., 2013a), we ~~have~~ assimilated the full SSH signal instead of the sea level anomaly (SLA), as in Verrier et al. (2017). As proposed by Errico et al. (2013), the back-ground error and observation-error statistics are specified as in the operational system for SST and in-situ observations, and the same quality control and data selection procedures are used ~~either~~  
5 ~~considering~~considering either simulated or real data in order to obtain results in the OSSEs that can match ~~with those from~~ a real ocean analysis. A specific OSSE, not shown here, was performed for calibration purpose mimicking the present altimetric observing systems with a 3 cm observation error prescribed on along-track observations, instead of 1 cm, ~~as~~ chosen for OSSE1 (Section 3) presented in this paper. In the open ocean, the innovations statistics to the along-track observations in this OSSE and in the IBI system assimilating real observations have a similar amplitude and patterns.

## 10 2.3 Simulation of observations

### 2.3.1 Sea-surface temperature (SST) and Temperature and Salinity profiles

To accurately ~~evaluate~~assess the impact of satellite altimetry data on ~~the~~ ocean analyses and forecasts, the same synthetic observations of SST, T and S profiles were considered in all the experiments. ~~We used daily averages of the NR to simulate the satellite SST maps. One daily SST map is used during the~~ An SST map representing a daily average is assimilated during each  
15 5-day assimilation cycle. Figure 2 shows an example of a synthetic SST field to be assimilated for ~~the~~ 15/06/2009. Temperature and salinity profiles are extracted at the same points and the same dates as the real in-situ profiles found in the CORA3.2 data base from CORIOLIS data ~~center~~centre (Cabanes et al., 2013). Figure 1, right panels, shows the number of T and S profiles available during 2009 over the IBI region.

### 2.3.2 Satellite altimetry data

20 In order to investigate the impact of different constellations of satellite altimeters, both conventional ~~along track~~along-track and wide-swath altimetry measurements were considered. Conventional altimetry data were derived from sampling the NR over the theoretical tracks of the satellite missions Jason 2, Cryosat 2 and Sentinel 3a, with a sampling frequency of 1 Hz (~ 7 km spatial sampling; e.g. Roblou et al. 2011). An observation white noise of 1 cm ~~rms~~root mean square was simulated and added to these pseudo-observations. Using the same approach, wide-swath data were derived considering a 20.9~~days~~day repeat orbit  
25 at a spatial resolution of ~~of~~ 7 km along and across the swath. In order to investigate the impact of multiple wide-swath altimeter missions, the data were derived by simulating two wide-swath altimeters, hereafter Swath-1 and Swath-2, obtained considering a 10-day shift in the orbits of the simulated missions. Figure 2 shows the spatial coverage of simulated satellite altimetry data ~~during 5 days over a 5-day period~~ (analysis window) considering conventional nadir (top left panel), along Swath-1 (top central panel) and along Swath- 1 and 2 (top right panel) altimeter missions. The specifics for each satellite altimetry mission  
30 considered in this study are detailed in Table 2

### 2.3.3 Wide-swath altimetry data

As previously mentioned, wide-swath altimetry observations were by obtained sampling the NR in ~~order such a way as~~ to mimic wide-swath SSH measurements. A 7 km grid resolution was considered to be consistent with the horizontal resolution of the AR configuration. Wide-swath altimetry measurements can be characterized by correlated and uncorrelated errors. ~~A~~  
5 Several studies have given a detailed description of ~~the~~ wide-swath (SWOT-like) altimetry errors ~~is given by several works~~  
~~in the literature~~ (e.g. Esteban Fernandez et al., 2014; Dibarboure and Ubelmann, 2014; Gaultier et al., 2016a; Ubelmann  
et al., 2015; Ruggiero et al., 2016). Aware of the importance of a full characterization of the errors to exploit the information  
coming from wide-swath altimetry data (Ubelmann et al., 2017), as a first attempt to investigate their contribution to the ocean  
analyses and forecasts we focus only on the instrumental ~~uncorrelated~~ uncorrelated errors due to the radar interferometer  
10 (thermal noise) and on their cross-track variability. Figure 2, bottom left panel, shows the standard deviation of the random  
error obtained considering different radar interferometer configurations and ~~an across swath horizontal resolution~~ across swath  
horizontal resolutions of 1 and 7 km. In this sense, it is important to notice that the error has marked spatial variability across  
the swath, reaching the highest values at the edges and the lowest near the inner part of the swath.

The measurement errors ~~of caused by~~ the radar interferometer were defined in collaboration with TAS, contractor of radar  
15 altimeters for EO in Europe. In this study, the error due to a Ku-band Klystron Dual Receive Antenna (DRA) was considered  
and a cross-track spatial resolution of 7 km was selected to be consistent with the resolution of the simulated satellite altimetry  
data.

### 3 Experimental set-up: OSSEs

In this section we describe the set-up design of the OSSEs performed to investigate the impact of wide-swath altimetry data  
20 once assimilated in an ocean monitoring and forecasting system in the IBI region.

First, a reference experiment, hereafter OSSE0, was ~~realized performed~~ considering the AR configuration but without any  
synthetic observation. ~~Other four different OSSEs have been~~ Four other different OSSEs were carried out varying the type  
and number of altimeter missions considered. To evaluate assess how the constellation of nadir altimeters constrain the ocean  
analysis and forecast, an experiment was ~~realized performed~~ considering exclusively conventional nadir altimeters (Jason-  
25 1, Cryosat-2, Sentinel-3a), hereafter OSSE1, ~~considering assuming~~ an instrumental error ~~in the order~~ of 1 *cm*. A second  
experiment, hereafter OSSE2, was performed considering nadir altimeters and Swath-1 data to address the question ~~about of~~  
the impact of ~~having in the~~ future SSH measurements based on both nadir and wide-swath altimeter missions. As already  
mentioned, SWOT-like data have a temporal resolution which ~~could not allow to resolve correctly~~ does not allow  
the evolution of mesoscale structures to be resolved correctly. In order to investigate the impact of the ~~repetitivity repeat cycle~~  
30 swath altimetry data, in the experiment OSSE3 an additional wide-swath altimeter was considered, relative to OSSE2. This  
first series of OSSEs (OSSE2 and OSSE3) was performed assimilating wide-swath altimetry data simulated assuming a radar  
interferometer error that ranged between 0.8 *cm* in the inner part of the swath and 2 *cm* ~~on at~~ the outer edges. The ~~order of~~  
~~magnitude of the~~ instrumental error was selected, in close collaboration with TAS, to consider less stringent noise requirements

compared to [the](#) NASA/CNES SWOT mission. In particular, we considered an instrumental error four times larger than the error prescribed for the Ka-band Radar Interferometer (KaRIN) onboard the SWOT mission (TAS technical report). The bottom left panel in Figure 2, shows the across swath error obtained considering a spatial resolution both at 1 km (black line) and 7 km (orange line). In order to investigate the sensitivity of the ocean analysis and forecasting system to the error of [a](#) wide-swath altimetry instrument, a dedicated OSSE, hereafter OSSE4, was ~~realized~~ [performed](#) considering a satellite constellation as in OSSE3 but assuming a radar interferometer error ~~which has an halved of one half the~~ order of magnitude (0.4 - 1 cm) with respect to the other OSSEs (2 x KaRIN error). The [error values in OSSE4 represent one of the solutions analyzed by TAS, as part of this ESA study, to develop European wide-swath altimetry concepts.](#) The experimental set-up used in this study is ~~listed~~ [detailed](#) in Table 3.

#### 10 4 Impact on sea-level analyses and forecasts

In this section we compare the SSH in the different OSSEs, with the “truth” SSH given by the NR. Figure 3 shows the SSH variance in the ~~NatRunNR~~, computed over the period ~~February—December~~ [February-December](#) 2009. The IBI region is characterized by ~~relatively steep a relatively steep bathymetric~~ slope separating the deep ocean from the shelf (Maraldi et al., 2013). On the continental shelves, the barotropic component of the SSH has a dominant signature. Preliminary findings of this work showed that this kind of variability was ~~captured also also captured~~ in the reference simulation (OSSE0), without data assimilation, while in the deeper areas of the ocean it was not accurately reproduced and the variance of the error was larger than 50 % of the variance of the NR (not shown). To ~~evaluate the results we considered~~ [assess the results, we considered the relative variance](#)  $VAR^*$  defined (in terms of percentage) as:

$$VAR^* = 100 \frac{VarError(OSSE_k)}{Var(NR)} \quad (1)$$

20 where  $VarError$  is the variance of the error obtained [by](#) comparing a given OSSE with the NR,  $k$  refers to the  $k$ th experiments and  $Var(NR)$  is the variance of the signals in the NR. [In particular  \$VarError\$  and  \$Var\(NR\)\$  are spatial maps of temporal variance, which \(considering SSH data\), are defined as](#)

$$VarError = \frac{\sum_{t=0}^{t=T} (SSH_{OSSE_k}(x, y, t) - SSH_{NR}(x, y, t))^2}{n_t} - \left( \frac{\sum_{t=0}^{t=T} (SSH_{OSSE_k}(x, y, t) - SSH_{NR}(x, y, t))}{n_t} \right)^2$$

$$Var(NR) = \frac{\sum_{t=0}^{t=T} SSH_{NR}(x, y, t)^2}{n_t} - \left( \frac{\sum_{t=0}^{t=T} SSH_{NR}(x, y, t)}{n_t} \right)^2$$

25 [where  \$T\$  is the last temporal record and  \$n\_t\$  the number of temporal records considered.](#)

In the following part of this Section, the results are ~~presented also also presented~~ in terms of contribution of wide-swath altimetry data to the reduction of ~~the~~ error (ER\*), both in ~~the~~ ocean analysis and ~~forecast~~ [forecasting](#). In order to ~~asses~~ [assess](#)

the impact of future satellite missions with respect to the current constellation of nadir altimeters, ~~the~~  $ER^*$  is defined as the percentage decrease of the error with respect to ~~the~~ OSSE1, i.e.

$$ER^* = 100 \frac{VarError(OSSE1) - VarError(OSSE_k)}{VarError(OSSE1)} \quad (2)$$

where  $VarError$  is defined as in Eq.(1), and  $k$  refers to the  $k$ th experiments, with  $k = 2, \dots, 4$ . A value of 50 % means that the variance of the error in the  $k$ th experiment has halved with respect to OSSE1.

Wide-swath altimetry data are expected to ~~provide a significant contribution to resolve the~~ contribute significantly to resolving mesoscale and sub-mesoscale variability in the ocean, which can have different spatial scales defined by the Rossby ~~deformation radius~~ radius of deformation in the different regions of the ocean. As shown in Hallberg (2013), over the shelf in the Celtic and North Seas ~~an a~~ higher horizontal resolution ( $1/50^\circ$ ) is needed to resolve the first baroclinic instability mode than the one used in the OSSEs ( $1/12^\circ$ ), which ~~instead results as being~~ is nonetheless suitable for resolving the ocean dynamics in the Atlantic. Thus, in our configurations we expect to observe the contribution of altimetry data in the OSSEs ~~is expected to be more evident~~ more clearly in the open ocean than over the continental shelf. In order to take into account the effects of the SSH barotropic component and of the spatial resolution over the shelves, the results in the OSSEs were ~~evaluated~~ assessed both over the entire IBI domain and considering the ocean areas with a bathymetry deeper than 200 metres (Table 4), which is the isobath that typically ~~represent~~ represents the separation between continental slope and shelf in the bathymetry adopted by the OGCMs used in the OSSEs (Maraldi et al., 2013).

In the experiment ~~which that~~ considers only nadir altimeters (OSSE1) ~~the error of the SSH in the ocean analysis represents ~~~ , the error regarding SSH in ocean analysis is 20-30 % of the variance of the SSH signal in the NR ( $VAR^*$  in Table 4). Large errors were observed in occurrence of the main features of the ocean circulation in the IBI region, both in the northern (e.g. North Atlantic Drift) and southern part of the domain (e. g. Azores Current), as well as in the Bay of Biscay.

One of the most significant results of this ~~work is about~~ study concern the impact of a constellation of satellites ~~which combines~~ combining nadir altimeters and one wide-swath instrument (OSSE2). Comparing the SSH in ~~the~~ ocean analysis with the "truth" data, the results showed a significant positive impact ~~in-on~~ the system and a reduction of the variance of the error ( $ER^*$ ) ~~up to order of of up to~~ ~ 30% was observed, with respect to the error observed assimilating the data of a constellation of three conventional altimeters (Figure 4). It is interesting to ~~notice that taking out note that, if~~ the shelf areas ~~were excluded,~~ the variance of the error increased in OSSE1, while in the experiments with wide-swath data ~~had a similar order, with respect to the error a similar degree of error was~~ observed over the whole domain ( $VarError$  in Table 4), underlining the impact of future measurements in the open ocean. As a consequence, the  $ER^*$  in OSSE2 ~~increased up to the order of ~ 35% considering the for~~ ocean areas with a bathymetry deeper than 200 metres ~~, with respect to was ~ 35% greater than for~~ OSSE1 over the same spatial domain. The impact of wide-swath altimetry measurements can be noticed over the entire spatial domain and in particular in the areas of the ocean characterized by the signature of the North Atlantic, Azores and Canary Currents and in the occurrence of mesoscale eddies in the Bay of Biscay, where large errors were observed considering only nadir altimeters.

In terms of  $VAR^*$ , OSSE2 also shows a  $VAR^*$  was also 6 % reduction with respect to lower for OSSE2 than for OSSE1. A larger impact was observed in the ocean forecast (Figure 5), where the  $ER^*$  increased up to the order of by about  $\sim 20$  %, considering the last (5th) day of ocean forecast (Table 5). When nadir altimeters were combined with a constellation of two wide-swath altimeters (OSSE3), the impact on the ocean analysis and forecasting system was even more significant, with an  $ER^*$  in the order of of approximately 40-45 % considering the entire IBI domain. The impact of the repetitivity of wide-swath data can be noticed comparing the results in A comparison of the results of OSSE3 and OSSE2 shows the impact of the higher repeat cycle of wide-swath data. A difference of  $\sim 10$  %, in terms of  $ER^*$ , was observed considering the data of two wide-swath missions in OSSE3, with respect to those obtained assimilating a single wide-swath altimeter in OSSE2. The positive impact observed was mainly due to improvements in the representation of SSH variability in the Bay of Biscay and in the occurrence of the Azores current (Figure 6). Inter-comparing OSSE2 and OSSE3, it is also interesting to notice the impact on the forecasting of the SSH. A constellation of two wide-swath altimeters shows a significant  $ER^*$  in the ocean forecast till the 5th day (  $\sim 28$  %) day of forecast, which almost corresponds to the error reduction observed at the 1st day of forecast (Table 5) considering only a single wide-swath altimeter (29 %).

Looking at the sensitivity of the system to the instrumental error of wide-swath data, a smaller radar interferometer noise was used in OSSE4 (0.4 - 1 cm), relative to the error used in other OSSEs. The results showed a larger  $ER^*$ , in the order of 7-8 % (Figure 6), with respect to the experiment which consider considering the same constellation of satellite altimeters (OSSE3) but a larger instrumental error (0.8 - 2 cm). In particular in OSSE4 was observed This involve a further improvement in representing the ocean dynamics due to the main ocean currents and mesoscale structures which characterize the SSH variability in the IBI region.

In particular, the largest  $ER^*$  ( $\sim 50$  %) was observed in OSSE4 and the errors represent the smallest portion (10-15 %) of the "observed" ocean variability ( $VAR^*$ ).

The results of the impact of wide-swath altimetry data on the representation of the SSH in the SSH in ocean analysis are summarized in Table 4.

## 5 Spectral analysis and coherence

In this Section we describe the results obtained in the OSSEs in terms of the representation of the ocean dynamics, looking at the errors over different spatial scales of variability.

The impact of wide-swath altimetry data in the OSSEs was evaluated assessed by a power spectra comparison, considering an open ocean area representative of the North Atlantic Drift (19 W°, 10 W°; 46°N, 55°N). This region is defined as an intermediate mesoscale variability region in the global ocean (Garçon et al., 2001) and represents is one of the regions which show the highest variability of the ocean circulation within the IBI domain. In particular here we, we here focus on the impact of wide-swath altimetry on the SSH at the different spatial scales. A wavelength window between 400 and 12 km was selected in order to clearly represent the energy content of the SSH signal in the sub-domain, given the spatial resolution of the OGCM used to perform the OSSEs. The analysis of spectra in a variance preserving form (Thomson and Emery, 2014) is shown in

Figure 7. The power spectra of the error (left panel) clearly show the differences among the OSSEs. ~~In order to evaluate also the impact of nadir altimeters, here~~ Here the reduction of the error at the different wavelength ( $ER_{spec}$ ) is defined as the percentage decrease of the error with respect to OSSE0 (Table 6), ~~in order to assess also the impact of nadir altimeters.~~

Considering nadir altimeters (blue curve), the impact on ~~the ocean analysis can be noticed~~ ocean analysis is noticeable at spatial scales down to 100 km ~~and an~~, ~~while is weaken at wavelengths of 50 km.~~ An  $ER_{spec}$  ~~in the order of of up to~~ 60 % was observed at wavelengths between 100 and 200 km. Significantly larger contributions were observed considering wide-swath altimetry data ( $ER_{spec}$  up to > 80 %). ~~Inter-comparing~~ Comparing the results in OSSE1 with those obtained in the other experiments (Figure 7, left panel; Table 6), the reduction of ~~the~~ error at these ~~length~~ scales ranged between 40 and 55 %. This is in agreement with Dufau et al. (2016) who, investigating the resolution capability of present and future altimetry missions, ~~observed that wide-swath altimetry will provide an unprecedented insight into the mesoscale ocean dynamics, with respect to along-track data. Here it is also interesting to notice the difference among~~ note that the difference between OSSE2 and OSSE3 (purple and ~~red lines~~), ~~which show orange lines~~ is small, ~~while is significant comparing OSSE2 and OSSE4 (green line) showing the impact of the repetitivity higher repeat cycle of the SSH measurements once a second and the sensitivity of the system to the error of a wide-swath altimeter was considered within the constellation of altimeters instrument.~~

The contribution of wide-swath altimetry data was also significant at spatial scales smaller than 100 km, which was not the case ~~considering when~~ only nadir altimeters ~~were considered~~. In particular, considering wavelengths between 50 and ~~100 km~~ 100 km, wide-swath altimetry data showed the largest contribution, with respect to along-track data. At these spatial scales, the  $ER_{spec}$  in OSSE1 was the lowest (10 %) observed in the spectral analysis. Combining nadir altimeters with one wide-swath instrument (OSSE2), the results showed an  $ER_{spec}$  ~~in the order of~~ 28 %. The introduction of a second wide-swath altimeter in OSSE3, assuming the same instrumental error ~~as that~~ used in OSSE2, showed a small further reduction of ~~the~~ error (30 %). On the other hand, considering a lower radar interferometer induced error in OSSE4 enhanced the system ~~to better resolve the~~, ~~making it capable to better resolving~~ ocean dynamics at these scales of variability and the largest  $ER_{spec}$  (> 38 %) was observed, underlining the sensitivity of the system to ~~the error of error in~~ wide-swath measurements.

~~A coherency~~ A coherence analysis (Thomson and Emery, 2014) was also performed to investigate the reliability of the SSH signal in the OSSEs at the different spatial scales, with respect to the NR (Figure 7 right panel). Spectral coherence is typically defined as the correlation between two signals as a function of wavelength (Ubelmann et al., 2015; Ponte and Klein, 2013; Klein et al., 2004). The spectral coherence between the SSH signals in the NR and in the OSSEs is defined as follow:

$$C_{spec} = \frac{C_{r_s}(NR, OSSE_k)}{S(NR) S(OSSE_k)} \quad (3)$$

where  $C_{r_s}$  and  $S$  represent the cross-spectral density and spectral density, respectively, of the signals and  $k$  refers to ~~kth~~ the  $k^{th}$  experiment.

Differences ~~among between~~ the OSSEs in terms of spectral coherence can be ~~noticed seen~~ down to spatial scales between 50 and 100 km. The assimilation of wide-swath altimetry data increased significantly the coherence between the SSH signals, ~~with respect to the experiment which compared with the experiment that~~ considers only nadir altimeters. At the large scale

(200-400 km), the coherence between the SSH signals was fairly high ( $> 0.8$ ) in all the OSSEs. Considering the coherence values at relevant spatial scales, it is possible to ~~inter-compare~~ compare the results in each experiment, as shown in Table 6. In particular, a different ~~coherency~~ coherence value observed at the same length scales in the OSSEs ~~provide evidences~~ provides evidence about the increased (decreased) level of reliability obtained considering (neglecting) a given observing system. At 5 spatial scales between 100 and 200 km, the coherence increased by 20 % when considering one wide-swath and the nadir altimeters (OSSE2) ~~relative,~~ compared to OSSE1. Similar values were observed ~~considering for~~ two wide-swath altimeters in OSSE3. Looking at the sensitivity of the system to ~~the radar interferometer~~ radar interferometer induced error, the observing system designed in OSSE4 had the most significant impact on the spectral coherence in ~~the~~ ocean analysis at these spatial scales, relative to OSSE1 ( $> 20$  %). At the small scales ( $< 90$  km) the coherence was lower than 0.4 in all the experiments. 10 Aware of the limited significance of low ~~coherency~~ coherence values ( $< 0.5$ ), ~~here we we here~~ compare the results obtained in the OSSEs in order to obtain a qualitative ~~evaluation~~ assessment of the impact of the forthcoming altimeters on the spatial scales smaller than 100 km. At these wavelengths the coherence in OSSE1 was always in all cases lower than in the other OSSEs and the system was sensitive to the ~~repetitivity~~ higher repeat cycle of the wide-swath measurements considered: ~~introducing when~~ the data of one (OSSE2) and two (OSSE3) wide-swath altimeters were included, the coherence of the SSH signals in ~~the~~ ocean 15 analysis increased accordingly. The difference between the results of OSSE3 and OSSE4 was not significant ( $C_{spec}$  ranged between 0.2-0.4), even though ~~an higher coherency~~ greater qualitative coherence of the SSH signals due to more “accurate” wide-swath altimeters (Figure 7 right panel, green line) was ~~qualitatively noticed~~ observed down to spatial scales smaller than 70 km.

These results can be qualitatively extended to ~~the ocean forecast considered~~ ocean forecasting over the same spatial domain 20 (not shown). ~~The results of the spectral analysis, in terms of error and coherency, are summarized in Table 6.~~

## 6 Impact on velocity fields

In this Section we compare the contribution of wide-swath altimetry to the representation of the ocean circulation in the IBI region ~~considering for~~ ocean analyses. In order to investigate the reliability of ~~the~~ ocean circulation obtained in the different experiments, a comparison of the zonal and meridional currents was carried out, both at the surface and in the water column 25 (Table 7). Figure 8 shows the variance of the error obtained comparing the surface zonal velocities in the OSSEs with the same field in the NR ~~during over~~ a 2-month period (August-September 2009). In the Figure, the first panel shows the variance of the error obtained considering conventional nadir altimeters (OSSE1) and large errors were observed in the Atlantic. When wide-swath altimetry data were considered, a significant reduction of the error was observed, particularly evident in the North-Atlantic Drift, in the occurrence of the Azores Current and in the Bay of Biscay. In particular, considering a constellation of 30 three nadir and one wide-swath altimeters (OSSE2), an  $ER^*$  up to ~~the order of~~ 20 % was observed, ~~with respect~~ compared to the error observed considering only conventional altimeters. A larger impact on ~~the~~ ocean circulation at the surface ( $\sim 28$  %) was observed ~~considering when using~~ a constellation of three nadir and two wide-swath altimeters (OSSE3). Considering more accurate wide swath altimeters (OSSE4), the results showed a further reduction of the error in the domain ( $\sim 35$  %),

mainly due to an improved representation of the North Atlantic Current. Small positive  $ER^*$  differences (2-3 %), were observed ~~considering-when only~~ the ocean surface currents ~~only~~ in the deep ocean (> 200 m). ~~A coherency analysis performed considering-were taken into account. A coherence analysis performed concerning~~ the ocean currents (zonal and meridional) at the surface (not shown), confirmed the results observed ~~considering-concerning~~ the SSH fields. The results obtained for the zonal currents at the surface can ~~be-extended-also-also be extended~~ to the meridional currents, and in general to the ocean currents in the water column, as shown in Figure 9. The results of the comparison of the ocean currents in the OSSEs are summarized in Table 7.

## 7 Summary and conclusions

The contribution of wide-swath altimetry data ~~on-to~~ ocean analyses and forecasts was ~~evaluated-assessed~~ in the IBI region ~~during-over~~ a 1-year period (2009) by means of OSSEs. Five different experiments (4 OSSEs and 1 reference simulation, OSSE0) were designed simulating different constellations of satellites, composed ~~by-of~~ nadir and wide-swath altimeters, and the results compared with the NR. OSSE1 is representative of the ~~current~~ constellation of altimeters ~~at-present~~ and considers simulated data ~~of-from~~ three nadir altimeters (Jason2, Cryosa2 and Sentinel3a). Dedicated experiments performed for calibration ~~purposepurposes~~, prescribing a 3 cm observation error on along-track observations to mimic the present altimetric observing systems, showed ~~consistent-results-results consistent~~ with those derived ~~considering-using~~ real data in OSSEs ~~addressed-to-evaluate-designed to assess~~ the impact of multiple along-track altimeters in CMEMS systems.

OSSE2 differs from OSSE1 ~~due-to-by~~ the introduction of a wide-swath altimeter in the satellite constellation. The impact of the ~~repetitivity-of-swath-swath-repeat cycle of wide-swath~~ measurements was investigated in OSSE3, ~~considering-which included~~ a further wide-swath mission, ~~with-respect-in addition~~ to OSSE2. The sensitivity of the system to ~~the~~ wide-swath radar interferometer error was investigated in OSSE4, considering a lower instrumental error (0.4 - 1 cm) ~~with-respect-to-than~~ that used in the other experiments.

An initial result of this ~~work-regards-study concern~~ the reliability of the SSH signals that can be obtained considering different constellations of altimeter missions. Wide-swath SSH measurements ~~had-a-major-impact-to-reduce-the-error-in-the considerably reduced error in~~ ocean analyses and forecasts. A constellation of two (~~"accurate"~~) wide-swath altimeters ~~allow reducing-(OSSE4) reduced~~ the variance of ~~the~~ SSH errors by more than 50 % ~~with-respect-compared~~ to three conventional nadir altimeters, mainly due to an improved representation of ~~the~~ ocean mesoscale variability in areas of main ocean currents occurring in the IBI region (e.g. North Atlantic and Azores Currents). Looking at the SSH ocean forecasts, the most significant results were obtained ~~when~~ investigating the impact of two wide-swath altimeters. In particular the  $ER^*$  given by a constellation of three nadir altimeters and one wide-swath (3N+1S) mission ~~at-for~~ the first day of forecast ( $\sim 30$  %) is comparable ~~with-to~~ the  $ER^*$  obtained ~~at-for~~ the last (5th) day of forecast ~~considering-when~~ a second wide-swath altimeter (3N+2S) ~~in the satellites-is included in the satellite~~ constellation. The ~~last-aspect-inclusion of a second wide-swath altimeter~~ could have a strong implication for extending the temporal window in the ocean forecast. The ocean analysis and forecasting system used to perform the OSSEs was sensitive to the ~~repetitivity-repeat cycle~~ of wide-swath measurements and to the ~~instrumental~~

~~error caused by~~ wide-swath ~~altimeters-instrumental-error~~ ~~altimeters~~. The most significant results were obtained considering a constellation of three nadir and two "accurate" wide-swath altimeters ~~,which contributed to reduce (OSSE4; instrumental error 0.4-1 cm), which reduced~~ the error in ~~the ocean analysis up to the~~ ~~ocean analysis by up to~~  $\sim 10\%$  of the "observed" ocean variability ( $VAR^*$ ) in the (ocean) analysis.

5 ~~Evaluating~~ ~~When assessing~~ the SSH signals in the OSSEs by power spectra comparison and coherence analysis with the NR in one of the most energetic sub-regions in the IBI domain (North Atlantic Drift), the results showed that wide-swath altimetry data significantly contribute (40-50 %) to ~~resolve the~~ ~~the resolution of~~ ocean dynamics due to ~~the~~-mesoscale variability. This is ~~in~~ agreement with Dufau et al. (2016), ~~who~~ observed that wide-swath altimetry will provide an unprecedented insight into ~~the~~-mesoscale ocean dynamics, with respect to along-track data. A reduction of ~~the~~-error and an higher ~~coherency~~ ~~coherence~~ of the SSH signals can be ~~noticed~~ ~~observed~~ down to wavelengths  $< 100$  km ~~when~~ considering two accurate wide-swath altimeters within a future satellite constellation, relative to the ~~present~~ ~~current configuration~~. Similar results were ~~observed~~ ~~also considering the ocean forecast~~ ~~also observed considering ocean forecasts~~ and performing the same analysis on ~~the~~-ocean currents at the surface. The information provided by wide-swath data at the surface is ~~propagated, through the~~ ~~also applied, through~~ error covariances, ~~also~~ in the vertical ~~dimension~~ and has a considerable impact on the ocean circulation both at the surface and in the water column. Looking at the zonal currents and meridional currents at the surface and at depth, the error in the analysis was significantly reduced (~~by~~ 30 %) ~~considering with~~ two wide-swath instruments in the satellite constellation, relative to nadir altimeters. In particular, a reduction of the error down to  $\sim 10\%$  was observed on the ocean currents (up to 100 m) considering a constellation of two "accurate" wide-swath altimeters (OSSE4), with respect to wide-swath instruments with a larger observational error.

20 As already mentioned, the system used to ~~asses~~ ~~assess~~ the impact of ~~the~~-wide-swath altimetry data is sensitive to the instrumental (uncorrelated) errors due ~~the radar-interferometer~~ ~~Satellite to radar interefrometer noise~~. ~~Future~~ constellations of nadir and "accurate" wide-swath altimeters ~~would have in the future~~ ~~should have~~ a dramatic impact ~~to constrain for constraining~~ CMEMS ocean analysis and forecasting systems and their applications.

This study ~~represents is~~ a first effort to quantify the impact of a constellation of wide-swath altimeters on ocean analyses and forecasts. In the future, OSSEs should be performed in regions characterized by high mesoscale variability (~~i.e.e.g.~~ western boundary currents) to better assess the impact of ~~measurements~~ ~~measurement~~ errors in regions with ~~large signal to noise a~~ ~~large signal to noise~~ ratio. The sensitivity of results to the model spatial resolution should be assessed by performing OSSEs with a fully ~~eddy resolving~~ ~~eddy resolving~~ ocean model (e.g.  $1/36^\circ$ ). Finally, a full and accurate characterization of wide-swath ~~altimeters-error-spectrum~~ ~~altimeter error spectra~~ (Ubelmann et al., 2017) would allow the design of highly realistic OSSEs, ~~improving the definition of the error covariances required to combine wide-swath altimetry data and OGCMs through data assimilation techniques.~~

*Acknowledgements.* This work was supported by the European Space Agency (ESA) study on the potential role of wide-swath altimetry for the evolution of the European Union Copernicus Programme (contract ESA-Mercator Ocean n<sup>o</sup> ~~No.~~ 4000117621/16/NL/FF/gp).

## References


- Atlas, R., Hoffman, R. N., Ma, Z., Emmitt, G. D., Jr., S. A. W., Greco, S., Tucker, S., Bucci, L., Annane, B., Hardesty, R. M., and Murillo, S.: Observing System Simulation Experiments (OSSEs) to Evaluate the Potential Impact of an Optical Autocovariance Wind Lidar (OAWL) on Numerical Weather Prediction, *Journal of Atmospheric and Oceanic Technology*, 32, 1593–1613, <https://doi.org/10.1175/JTECH-D-15-0038.1>, 2015.
- 5     Barnier, B., Madec, G., Penduff, T., Molines, J.-M., Treguier, A.-M., Le Sommer, J., Beckmann, A., Biastoch, A., Böning, C., Dengg, J., Derval, C., Durand, E., Gulev, S., Remy, E., Talandier, C., Theetten, S., Maltrud, M., McClean, J., and De Cuevas, B.: Impact of partial steps and momentum advection schemes in a global ocean circulation model at eddy-permitting resolution, *Ocean Dynamics*, 56, 543–567, <https://doi.org/10.1007/s10236-006-0082-1>, <https://doi.org/10.1007/s10236-006-0082-1>, 2006.
- 10    Bell, M., Schiller, A., Traon, P.-Y. L., Smith, N., Dombrowsky, E., and Wilmer-Becker, K.: An introduction to GODAE OceanView, *Journal of Operational Oceanography*, 8, s2–s11, <https://doi.org/10.1080/1755876X.2015.1022041>, 2015.
- Benkiran, M. and Greiner, E.: Impact of the Incremental Analysis Updates on a Real-Time System of the North Atlantic Ocean, *Journal of Atmospheric and Oceanic Technology*, 25, 2055–2073, <https://doi.org/10.1175/2008JTECHO537.1>, <https://doi.org/10.1175/2008JTECHO537.1>, 2008.
- 15    Bloom, S. C., Takacs, L. L., da Silva, A. M., and Ledvina, D.: Data Assimilation Using Incremental Analysis Updates, *Monthly Weather Review*, 124, 1256–1271, [https://doi.org/10.1175/1520-0493\(1996\)124<1256:DAUIAU>2.0.CO;2](https://doi.org/10.1175/1520-0493(1996)124<1256:DAUIAU>2.0.CO;2), [https://doi.org/10.1175/1520-0493\(1996\)124<1256:DAUIAU>2.0.CO;2](https://doi.org/10.1175/1520-0493(1996)124<1256:DAUIAU>2.0.CO;2), 1996.
- Cabanes, C., Grouazel, A., von Schuckmann, K., Hamon, M., Turpin, V., Coatanoan, C., Paris, F., Guinehut, S., Boone, C., Ferry, N., de Boyer Montégut, C., Carval, T., Reverdin, G., Pouliquen, S., and Le Traon, P.-Y.: The CORA dataset: validation and diagnostics of in-situ ocean temperature and salinity measurements, 9, 1–18, <https://doi.org/10.5194/os-9-1-2013>, <http://www.ocean-sci.net/9/1/2013/>, 2013.
- 20    Dee, D., Uppala, S., Simmons, A., Berrisford, P., Poli, P., Kobayashi, S., Andrae, U., Balmaseda, M., Balsamo, G., Bauer, P., et al.: The ERA-Interim reanalysis: Configuration and performance of the data assimilation system, *Quarterly Journal of the Royal Meteorological Society*, 137, 553–597, 2011.
- 25    Dibarboure, G. and Ubelmann, C.: Investigating the Performance of Four Empirical Cross-Calibration Methods for the Proposed SWOT Mission, *Remote Sensing*, 6, 4831–4869, <https://doi.org/10.3390/rs6064831>, <http://www.mdpi.com/2072-4292/6/6/4831>, 2014.
- Dibarboure, G., Pujol, M.-I., Briol, F., Le Traon, P. Y., Larnicol, G., Picot, N., Mertz, F., and Ablain, M.: Jason-2 in DU-ACS: Updated System Description, First Tandem Results and Impact on Processing and Products, *Marine Geodesy*, 34, 214–241, <https://doi.org/10.1080/01490419.2011.584826>, <https://doi.org/10.1080/01490419.2011.584826>, 2011.
- 30    Donlon, C., Berruti, B., Buongiorno, A., Ferreira, M.-H., Féménias, P., Frerick, J., Goryl, P., Klein, U., Laur, H., Mavrocordatos, C., Nieke, J., Rebhan, H., Seitz, B., Stroede, J., and Sciarra, R.: The Global Monitoring for Environment and Security (GMES) Sentinel-3 mission, *Remote Sensing of Environment*, 120, 37 – 57, <https://doi.org/https://doi.org/10.1016/j.rse.2011.07.024>, <http://www.sciencedirect.com/science/article/pii/S0034425712000685>, the Sentinel Missions - New Opportunities for Science, 2012.
- Ducet, N., Le Traon, P. Y., and Reverdin, G.: Global high-resolution mapping of ocean circulation from TOPEX/Poseidon and ERS-1 and-2, 35     *Journal of Geophysical Research-Oceans*, 105, 2000.

- Dufau, C., Orszynowicz, M., Dibarboure, G., Morrow, R., and Le Traon, P.-Y.: Mesoscale resolution capability of altimetry: Present and future, *Journal of Geophysical Research: Oceans*, 121, 4910–4927, <https://doi.org/10.1002/2015JC010904>, <http://dx.doi.org/10.1002/2015JC010904>, 2016.
- Durand, M., Fu, L.-L., Lettenmaier, D. P., Alsdorf, D. E., Rodriguez, E., and Esteban-Fernandez, D.: The surface water and ocean topography mission: Observing terrestrial surface water and oceanic submesoscale eddies, *Proceedings of the IEEE*, 98, 766–779, 2010.
- Egbert, G. D. and Erofeeva, S. Y.: Efficient Inverse Modeling of Barotropic Ocean Tides, *Journal of Atmospheric and Oceanic Technology*, 19, 183–204, [https://doi.org/10.1175/1520-0426\(2002\)019<0183:EIMOBO>2.0.CO;2](https://doi.org/10.1175/1520-0426(2002)019<0183:EIMOBO>2.0.CO;2), 2002.
- Errico, R. M., Yang, R., Privé, N. C., Tai, K.-S., Todling, R., Sienkiewicz, M. E., and Guo, J.: Development and validation of observing-system simulation experiments at NASA’s Global Modeling and Assimilation Office, *Quarterly Journal of the Royal Meteorological Society*, 139, 1162–1178, <https://doi.org/10.1002/qj.2027>, <http://dx.doi.org/10.1002/qj.2027>, 2013.
- Esteban Fernandez, D., Pollard, B., Vaze, P., and Abelson, R.: Swot Project Mission Performance and Error Budget, Tech. Rep. JPL D-79084, p. 83, <https://swot.jpl.nasa.gov/science/resources>, 2014.
- Fu, L.-L. and Chelton, D. B.: Chapter 2 Large-Scale Ocean Circulation, in: *Satellite Altimetry and Earth Sciences*, edited by Fu, L.-L. and Cazenave, A., vol. 69 of *International Geophysics*, pp. 133 – viii, Academic Press, [https://doi.org/https://doi.org/10.1016/S0074-6142\(01\)80147-9](https://doi.org/https://doi.org/10.1016/S0074-6142(01)80147-9), <http://www.sciencedirect.com/science/article/pii/S0074614201801479>, 2001.
- Fu, L.-L. and Ferrari, R.: Observing Oceanic Submesoscale Processes From Space, *Eos, Transactions American Geophysical Union*, 89, 488–488, <https://doi.org/10.1029/2008EO480003>, <http://dx.doi.org/10.1029/2008EO480003>, 2008.
- Fu, L.-L., Alsdorf, D., Rodriguez, E., Morrow, R., Mognard, N., Lambin, J., Vaze, P., and Lafon, T.: The SWOT (Surface Water and Ocean Topography) mission: spaceborne radar interferometry for oceanographic and hydrological applications, in: *OCEANOBS’09 Conference*, 2009.
- Garric, G., Parent, L., Greiner, E., Drévilion, M., Hamon, M., Lellouche, J., Régnier, C., Desportes C. and, Le Galloudec, O., Bricaud, C., Drillet, Y., Hernandez, F., Dubois, C., and Le Traon, P. Y.: Performance and quality assessment of the global ocean eddy-permitting physical reanalysis GLORYS2V4. Operational Oceanography serving Sustainable Marine Development, in: *Proceedings of the Eight EuroGOOS International Conference. 3-5 October 2017, Bergen, Norway*. E. Buch, V. Fernandez, G. Nolan and D. Eparkhina (Eds.) EuroGOOS. Brussels, Belgium. 2018. ISBN 978-2-9601883-3-2. 516 pp, 2018.
- Garçon, V. C., Oschlies, A., Doney, S. C., McGillicuddy, D., and Waniek, J.: The role of mesoscale variability on plankton dynamics in the North Atlantic, *Deep Sea Research Part II: Topical Studies in Oceanography*, 48, 2199 – 2226, [https://doi.org/https://doi.org/10.1016/S0967-0645\(00\)00183-1](https://doi.org/https://doi.org/10.1016/S0967-0645(00)00183-1), <http://www.sciencedirect.com/science/article/pii/S0967064500001831>, *jGOFS Research in the North Atlantic Ocean: A Decade of Research, Synthesis and modelling*, 2001.
- Gaultier, L., Ubelmann, C., and Fu, L.-L.: The Challenge of Using Future SWOT Data for Oceanic Field Reconstruction, *Journal of Atmospheric and Oceanic Technology*, 33, 119–126, <https://doi.org/10.1175/JTECH-D-15-0160.1>, <http://dx.doi.org/10.1175/JTECH-D-15-0160.1>, 2016a.
- Gaultier, L., Ubelmann, C., and Fu, L.-L.: The Challenge of Using Future SWOT Data for Oceanic Field Reconstruction, *Journal of Atmospheric and Oceanic Technology*, 33, 119–126, <https://doi.org/10.1175/JTECH-D-15-0160.1>, <http://dx.doi.org/10.1175/JTECH-D-15-0160.1>, 2016b.
- Hallberg, R.: Using a resolution function to regulate parameterizations of oceanic mesoscale eddy effects, *Ocean Modelling*, 72, 92 – 103, <https://doi.org/https://doi.org/10.1016/j.ocemod.2013.08.007>, <http://www.sciencedirect.com/science/article/pii/S1463500313001601>, 2013.


- Halliwel, G. R., Srinivasan, A., Kourafalou, V., Yang, H., Willey, D., Hénaff, M. L., and Atlas, R.: Rigorous Evaluation of a Fraternal Twin Ocean OSSE System for the Open Gulf of Mexico, *Journal of Atmospheric and Oceanic Technology*, 31, 105–130, <https://doi.org/10.1175/JTECH-D-13-00011.1>, 2014.
- 5 Halliwel, G. R., Mehari, M. F., Hénaff, M. L., Kourafalou, V. H., Androulidakis, I. S., Kang, H. S., and Atlas, R.: North Atlantic Ocean OSSE system: Evaluation of operational ocean observing system components and supplemental seasonal observations for potentially improving tropical cyclone prediction in coupled systems, *Journal of Operational Oceanography*, 10, 154–175, <https://doi.org/10.1080/1755876X.2017.1322770>, 2017.
- Hénaff, M. L., Mey, P. D., Mourre, B., and Traon, P.-Y. L.: Contribution of a Wide-Swath Altimeter in a Shelf Seas Assimilation System: Impact of the Satellite Roll Errors, *Journal of Atmospheric and Oceanic Technology*, 25, 2133–2144, <https://doi.org/10.1175/2008JTECHO576.1>, 2008.
- 10 Ide, K., Courtier, P., Ghil, M., and Lorenc, A. C.: Unified Notation for Data Assimilation: Operational, Sequential and Variational (gtSpecial IssueltData Assimilation in Meteorology and Oceanography: Theory and Practice), *Journal of the Meteorological Society of Japan. Ser. II*, 75, 181–189, 1997.
- Klein, P., Lapeyre, G., and Large, W. G.: Wind ringing of the ocean in presence of mesoscale eddies, *Geophysical Research Letters*, 31, <https://doi.org/10.1029/2004GL020274>, <http://dx.doi.org/10.1029/2004GL020274>, 115306, 2004.
- 15 Kourafalou, V. H., Androulidakis, Y. S., Halliwel, G. R., Kang, H., Mehari, M. M., Hénaff, M. L., Atlas, R., and Lumpkin, R.: North Atlantic Ocean OSSE system development: Nature Run evaluation and application to hurricane interaction with the Gulf Stream, *Progress in Oceanography*, 148, 1 – 25, <https://doi.org/https://doi.org/10.1016/j.pocean.2016.09.001>, <http://www.sciencedirect.com/science/article/pii/S0079661115300653>, 2016.
- 20 Le Traon, P. and Morrow, R.: Chapter 3 Ocean Currents and Eddies, in: *Satellite Altimetry and Earth Sciences*, edited by Fu, L.-L. and Cazenave, A., vol. 69 of *International Geophysics*, pp. 171 – xi, Academic Press, [https://doi.org/https://doi.org/10.1016/S0074-6142\(01\)80148-0](https://doi.org/https://doi.org/10.1016/S0074-6142(01)80148-0), <http://www.sciencedirect.com/science/article/pii/S0074614201801480>, 2001.
- Le Traon, P. Y.: From satellite altimetry to Argo and operational oceanography: three revolutions in oceanography, *Ocean Science*, 9, 901–915, <https://doi.org/10.5194/os-9-901-2013>, <https://www.ocean-sci.net/9/901/2013/>, 2013.
- 25 Le Traon, P. Y. and Dibarboure, G.: Mesoscale Mapping Capabilities of Multiple-Satellite Altimeter Missions, *Journal of Atmospheric and Oceanic Technology*, 16, 1208–1223, [https://doi.org/10.1175/1520-0426\(1999\)016<1208:MMCOMS>2.0.CO;2](https://doi.org/10.1175/1520-0426(1999)016<1208:MMCOMS>2.0.CO;2), 1999.
- Le Traon, P. Y., Antoine, D., Bentamy, A., Bonekamp, H., Breivik, L., Chapron, B., Corlett, G., Dibarboure, G., DiGiacomo, P., Donlon, C., Faugère, Y., Font, J., Girard-Ardhuin, F., Gohin, F., Johannessen, J., Kamachi, M., Lagerloef, G., Lambin, J., Larnicol, G., Borgne, P. L., Leuliette, E., Lindstrom, E., Martin, M., Maturi, E., Miller, L., Mingsen, L., Morrow, R., Reul, N., Rio, M., Roquet, H., Santoleri, R., and
- 30 Wilkin, J.: Use of satellite observations for operational oceanography: recent achievements and future prospects, *Journal of Operational Oceanography*, 8, s12–s27, <https://doi.org/10.1080/1755876X.2015.1022050>, 2015.
- Le Traon, P. Y., Ali, A., Alvarez Fanjul, E., Aouf, L., Axell, L., Aznar, R., Ballarotta, M., Behrens, A., Mounir, B., Bentamy, A., Bertino, L., Bowyer, P., Brando, V., A. Breivik, L., Buongiorno Nardelli, B., Cailleau, S., Ciliberti, S., Clementi, E., Colella, S., and Zuo, H.: The Copernicus Marine Environmental Monitoring Service: Main Scientific Achievements and Future Prospects, 56, 2017a.
- 35 Le Traon, P. Y., Dibarboure, G., Jacobs, G., Martin, G., Remy, E., and Schiller, A.: Use of satellite altimetry for operational oceanography, in: *Satellite Altimetry Over Oceans and Land Surfaces*, edited by Stammer, D. and Cazenave, A., CRC Press, 2017b.
- Lellouche, J.-M., Le Galloudec, O., Drévilion, M., Régnier, C., Greiner, E., Garric, G., Ferry, N., Desportes, C., Testut, C.-E., Bricaud, C., Bourdallé-Badie, R., Tranchant, B., Benkiran, M., Drillet, Y., Daudin, A., and De Nicola, C.: Evaluation of global monitoring and

- forecasting systems at Mercator Océan, *Ocean Science*, 9, 57–81, <https://doi.org/10.5194/os-9-57-2013>, <http://www.ocean-sci.net/9/57/2013/>, 2013a.
- Lellouche, J.-M., Le Galloudec, O., Drévilion, M., Régnier, C., Greiner, E., Garric, G., Ferry, N., Desportes, C., Testut, C.-E., Bricaud, C., Bourdallé-Badie, R., Tranchant, B., Benkiran, M., Drillet, Y., Daudin, A., and De Nicola, C.: Evaluation of global monitoring and forecasting systems at Mercator Océan, *Ocean Science*, 9, 57–81, <https://doi.org/10.5194/os-9-57-2013>, <http://www.ocean-sci.net/9/57/2013/>, 2013b.
- Lyard, F., Lefevre, F., Letellier, T., and Francis, O.: Modelling the global ocean tides: modern insights from FES2004, *Ocean Dynamics*, 56, 394–415, <https://doi.org/10.1007/s10236-006-0086-x>, <http://dx.doi.org/10.1007/s10236-006-0086-x>, 2006.
- Lyard, F., Carrere, L., Cancet, M., Guillot, A., and Picot, N.: FES2014, a new finite elements tidal model for global ocean, *Ocean Dynam.*, in preparation, 2017.
- Madec, G.: NEMO ocean engine, [http://www.nemo-ocean.eu/About-NEMO/Reference-manuals/NEMO\\_book\\_3.6\\_STABLE](http://www.nemo-ocean.eu/About-NEMO/Reference-manuals/NEMO_book_3.6_STABLE), 2016.
- Maraldi, C., Chanut, J., Levier, B., Ayoub, N., De Mey, P., Reffray, G., Lyard, F., Cailleau, S., Drévilion, M., Fanjul, E. A., Sotillo, M. G., Marsaleix, P., and Team, M.: NEMO on the shelf: assessment of the Iberia-Biscay-Ireland configuration., *Ocean Science*, 9, 745–771, <https://doi.org/10.5194/os-9-745-2013>, <https://hal.archives-ouvertes.fr/hal-00766544>, 2013.
- Morrow, R. and Le Traon, P.-Y.: Recent advances in observing mesoscale ocean dynamics with satellite altimetry, *Advances in Space Research*, 50, 1062 – 1076, <https://doi.org/https://doi.org/10.1016/j.asr.2011.09.033>, <http://www.sciencedirect.com/science/article/pii/S0273117711007150>, *oceanography, Cryosphere and Freshwater Flux to the Ocean*, 2012.
- Oddo, P., Bonaduce, A., Pinardi, N., and Guarneri, A.: Sensitivity of the Mediterranean sea level to atmospheric pressure and free surface elevation numerical formulation in NEMO, *Geoscientific Model Development*, under review, 2014.
- Oke, P., Larnicol, G., Fujii, Y., Smith, G., Lea, D., Guinehut, S., Remy, E., Balmaseda, M. A., Rykova, T., Surcel-Colan, D., Martin, M., Sellar, A., Mulet, S., and Turpin, V.: Assessing the impact of observations on ocean forecasts and reanalyses: Part 1, Global studies, *Journal of Operational Oceanography*, 8, s49–s62, <https://doi.org/10.1080/1755876X.2015.1022067>, 2015a.
- Oke, P., Larnicol, G., Jones, E., Kourafalou, V., Sperreik, A., Carse, F., Tanajura, C., Mourre, B., Tonani, M., Brassington, G., Henaff, M. L., Jr., G. H., Atlas, R., Moore, A., Edwards, C., Martin, M., Sellar, A., Alvarez, A., Mey, P. D., and Iskandarani, M.: Assessing the impact of observations on ocean forecasts and reanalyses: Part 2, Regional applications, *Journal of Operational Oceanography*, 8, s63–s79, <https://doi.org/10.1080/1755876X.2015.1022080>, 2015b.
- Oke, P. R. and Schiller, A.: Impact of Argo, SST, and altimeter data on an eddy-resolving ocean reanalysis, *Geophysical Research Letters*, 34, n/a–n/a, <https://doi.org/10.1029/2007GL031549>, <http://dx.doi.org/10.1029/2007GL031549>, I19601, 2007.
- Oke, P. R., Brassington, G. B., Griffin, D. A., and Schiller, A.: The Bluelink ocean data assimilation system (BODAS), *Ocean Modelling*, 21, 46 – 70, <https://doi.org/https://doi.org/10.1016/j.ocemod.2007.11.002>, <http://www.sciencedirect.com/science/article/pii/S1463500307001540>, 2008.
- Pascual, A., Faugère, Y., Larnicol, G., and Le Traon, P.-Y.: Improved description of the ocean mesoscale variability by combining four satellite altimeters, *Geophysical Research Letters*, 33, n/a–n/a, <https://doi.org/10.1029/2005GL024633>, <http://dx.doi.org/10.1029/2005GL024633>, I02611, 2006.
- Ponte, A. L. and Klein, P.: Reconstruction of the upper ocean 3D dynamics from high-resolution sea surface height, *Ocean Dynamics*, 63, 777–791, <https://doi.org/10.1007/s10236-013-0611-7>, <https://doi.org/10.1007/s10236-013-0611-7>, 2013.


- Pujol, M.-I., Dibarboure, G., Traon, P.-Y. L., and Klein, P.: Using High-Resolution Altimetry to Observe Mesoscale Signals, *Journal of Atmospheric and Oceanic Technology*, 29, 1409–1416, <https://doi.org/10.1175/JTECH-D-12-00032.1>, <https://doi.org/10.1175/JTECH-D-12-00032.1>, 2012.
- Roblou, L., Lamouroux, J., Bouffard, J., Lyard, F., Le Hénaff, M., Lombard, A., Marsaleix, P., De Mey, P., and Birol, F.: Post-processing  
5 Altimeter Data Towards Coastal Applications and Integration into Coastal Models, pp. 217–246, Springer Berlin Heidelberg, Berlin, Heidelberg, [https://doi.org/10.1007/978-3-642-12796-0\\_9](https://doi.org/10.1007/978-3-642-12796-0_9), [https://doi.org/10.1007/978-3-642-12796-0\\_9](https://doi.org/10.1007/978-3-642-12796-0_9), 2011.
- Ruggiero, G. A., Cosme, E., Brankart, J.-M., Sommer, J. L., and Ubelmann, C.: An efficient way to account for observation error correlations in the assimilation of data from the future SWOT High-Resolution altimeter mission, *Journal of Atmospheric and Oceanic Technology*, 0, null, <https://doi.org/10.1175/JTECH-D-16-0048.1>, <http://dx.doi.org/10.1175/JTECH-D-16-0048.1>, 2016.
- 10 Schiller, A., Bell, M., Brassington, G., Brasseur, P., Barciela, R., Mey, P. D., Dombrowsky, E., Gehlen, M., Hernandez, F., Kourafalou, V., Larnicol, G., Traon, P.-Y. L., Martin, M., Oke, P., Smith, G. C., Smith, N., Tolman, H., and Wilmer-Becker, K.: Synthesis of new scientific challenges for GODAE OceanView, *Journal of Operational Oceanography*, 8, s259–s271, <https://doi.org/10.1080/1755876X.2015.1049901>, 2015.
- Sotillo, M. G., Cailleau, S., Lorente, P., Levier, B., Aznar, R., Reffray, G., Amo-Baladrón, A., Chanut, J., Benkiran, M., and Alvarez-Fanjul,  
15 E.: The MyOcean IBI Ocean Forecast and Reanalysis Systems: operational products and roadmap to the future Copernicus Service, *Journal of Operational Oceanography*, 8, 63–79, <https://doi.org/10.1080/1755876X.2015.1014663>, <https://doi.org/10.1080/1755876X.2015.1014663>, 2015.
- Thomson, R. E. and Emery, W. J.: Chapter 5 - Time Series Analysis Methods, in: *Data Analysis Methods in Physical Oceanography (Third Edition)*, edited by Thomson, R. E. and Emery, W. J., pp. 425 – 591, Elsevier, Boston,  
20 third edition edn., <https://doi.org/https://doi.org/10.1016/B978-0-12-387782-6.00005-3>, <https://www.sciencedirect.com/science/article/pii/B9780123877826000053>, 2014.
- Ubelmann, C., Klein, P., and Fu, L.-L.: Dynamic Interpolation of Sea Surface Height and Potential Applications for Future High-Resolution Altimetry Mapping, *Journal of Atmospheric and Oceanic Technology*, 32, 177–184, <https://doi.org/10.1175/JTECH-D-14-00152.1>, <http://dx.doi.org/10.1175/JTECH-D-14-00152.1>, 2015.
- 25 Ubelmann, C., Dibarboure, G., and Dubois, P.: A cross-spectral approach to measure the error budget of the SWOT altimetry mission over the Ocean, *Journal of Atmospheric and Oceanic Technology*, 0, null, <https://doi.org/10.1175/JTECH-D-17-0061.1>, 2017.
- Verrier, S., Le Traon, P.-Y., and Remy, E.: Assessing the impact of multiple altimeter missions and Argo in a global eddy-permitting data assimilation system, *Ocean Science*, 13, 1077–1092, <https://doi.org/10.5194/os-13-1077-2017>, <https://www.ocean-sci.net/13/1077/2017/>, 2017.
- 30 Wunsch, C. and Stammer, D.: Atmospheric loading and the oceanic “inverted barometer” effect, *Reviews of Geophysics*, 35, 79–107, <https://doi.org/10.1029/96RG03037>, <http://onlinelibrary.wiley.com/doi/10.1029/96RG03037/abstract>, 1997.




**Figure 1.** Temperature and Salinity simulated data. Left panel: sea-surface temperature from the NR (15th June 2009). Right panels: number of temperature (top) and salinity (bottom) data during the year 2009 (corresponding to the database CORA3.2 in-situ data positions).




**Figure 2.** Satellite altimetry spatial coverage and wide-swath interferometer error. Top panels: satellite altimetry spatial coverage during one assimilation cycle (5 days); ~~from the~~ left: Jason2, Cryosat 2 and Sentinel 3a; ~~central~~: Swath-1; ~~right~~: Swath-1 Swath-2. Bottom panels: across swath error. Left: the curves displayed show the wide-swath instrumental error used to perform the experiments OSSE2 and OSSE3, considering an across swath horizontal resolution of 1 km (black line) and 7 km (orange line). The blue curve shows the instrumental error used in OSSE4. Right: along swath error given by the radar interferometer noise and along swath simulated data.




**Figure 3.** SSH variance in the NR over the period February-December 2009. Values expressed as  $[cm^2]$ .




**Figure 4.** Temporal evolution of the SSH error variance in the ocean analysis over the period February-December 2009. Results obtained comparing the SSH of the ocean analysis in the experiments OSSE1 (blue lines) and OSSE2 (purple line), OSSE3 (red-orange line) and OSSE4 (green line) with the data of the NR considering the ocean areas with a bathymetry deeper than 200 metres; y-axes expressed as  $[cm^2]$ . OSSE0 (not shown) ranged between 25 and 35  $cm^2$  .




**Figure 5.** Variance of the error for each day of forecast (5 days) considering the SSH, in regions with a bathymetry deeper than 200 metres, over the period from ~~February-February~~ to December 2009. The legend of the OSSEs is as in Figure 4; y-axis expressed as [cm<sup>2</sup>].




**Figure 6.** Maps of the variance of SSH error in the ocean analysis over the IBI domain during the period February-December 2009. The results are obtained comparing the SSH of the NR with the ocean analysis of the experiment OSSE1 (top left), OSSE2 (top central), OSSE3 (top right), OSSE4 (bottom left). Values expressed as  $[cm^2]$ .



**Figure 7.** Spectral Analysis of the SSH signals in the OSSEs considering an open ocean region (-19°W, -10°W; 46.N, 55°N) representative of the North Atlantic Drift, during the period February-December 2009. In the panels the results for the experiments OSSE0 (gray lines), OSSE1 (blue lines), OSSE2 (purple lines), OSSE3 (red-orange lines) and OSSE4 (green lines), are shown at the spectral window between 400 km and 12 km. Left panel: power spectra of the SSH error, with respect to the NR; the spectra are shown in a variance preserving form [ $cm^2$ ]. Right panel: spectral coherence in the OSSEs with respect to the NR; black dashed line shows the 95 % confidence interval (Thomson and Emery, 2014).



**Figure 8.** Ocean zonal currents at the surface: variance of misfits in the ocean analysis over the IBI domain during the period August-September 2009. The results are obtained comparing the zonal currents of the “truth data” with the ocean analysis in the experiment OSSE1 (top left), OSSE2 (top central), OSSE3 (top right), OSSE4 (bottom right) . Values expressed as  $[ 10^{-2} m^2 sec^{-2}]$ .



**Figure 9.** As in Figure 8 but considering ocean meridional currents at 100 metres depth.

**Table 1.** The nature run (NR) and assimilated run (AR) configurations. The rows show the OGCM configurations used to obtain the nature run (NR) and the assimilated run (AR). The columns show the OGCM used, the horizontal resolution (GRID), initial (IC) and boundary (BDC) conditions and the atmospheric forcings (ATM) considered in each configuration.

	OGCM	GRID	IC & BDC	ATM
NR	NEMO v3.6	1/36 °	Global Analysis (Lellouche et al., 2013b); Tides (FES; Lyard et al., 2017)	ECMWF Analysis
AR	NEMO v3.6	1/12 °	Global Re-analysis (GLORYS; Garric et al., 2018); Tides (IBI)	ECMWF Era-Interim (Dee et al., 2011)

**Table 2.** [Satellite altimetry missions characteristics](https://earth.esa.int/web/eoportal/satellite-missions) (<https://earth.esa.int/web/eoportal/satellite-missions>). The columns show the altimeters orbit parameters: repeat cycle (RC) expressed as *days*, footprint (FP) and cross-track separation (CTS) expressed as *km*. The rows show the altimeters considered in this study: Jason-2 (J2), Cryosat-2 (C2), Sentinel-3a (S3; Donlon et al., 2012) and Swath-1. In Swath-1, CTS is the distance of consecutive ocean cross-over points given by the overlap of an ascending and a descending pass (Esteban Fernandez et al., 2014).

	RC	FP	CTS
<b>J2</b>	<i>9.9 days</i>	<i>10 km</i>	<i>315 km</i>
<b>C2</b>	<i>369</i>	<i>15</i>	<i>&gt; 7.5</i>
<b>S3</b>	<i>27</i>	<i>18</i>	<i>104</i>
<b>Swath-1</b>	<i>20.9</i>	<i>120</i>	<i>500</i>

**Table 3.** OSSEs experimental set-up. The rows show the name of the relevant experiment, while columns detail the observations considered in the analysis. Column 1 shows the nadir altimeters considered in the OSSEs: Jason2 (J2), Cryosat 2 (C2), Sentinel 3a (S3). Last Column shows the instrumental error (expressed as *cm*) used to simulate the altimetry data; OSSE2-OSSE4: range of across swath errors considered for the wide-swath altimetry data. In the round brackets: reference simulation without data assimilation (Free); three nadir altimeters (3N); one wide-swath (1S); two wide-swath (2S); Lower radar interferometer Error (LE). In the squared brackets: order of magnitude of wide-swath altimetry error selected in the OSSEs, with respect to the error of KaRIN instrument (NASA/CNES SWOT mission).

	J2,C2,S3	Swath-1	Swath-2	T&S	SST	Error
<b>OSSE0 (Free)</b>						
<b>OSSE1 (3N)</b>	YES			YES	YES	1
<b>OSSE2 (3N+1S)</b>	YES	YES		YES	YES	0.8-2 [4 x KaRIN]
<b>OSSE3 (3N+2S)</b>	YES	YES	YES	YES	YES	0.8-2 [4 x KaRIN]
<b>OSSE4 (3N+2S+LE)</b>	YES	YES	YES	YES	YES	0.4-1 [2 x KaRIN]

**Table 4.** Ocean Analysis statistics considering the SSH fields during the year 2009. Column 1: ocean analysis variance of error with respect to the NR (VarError [ $cm^2$ ]). Column 2: reduction of the variance of the error in the ocean analysis (ER [%]), with respect to OSSE1 (3N). Column 3: ratio among the variance of the error in each experiment and the variance of the SSH signal in the NR (VAR\* [%]). Column 4-6: as in Columns 1-3, but excluding the shelves areas shallower than 200 metres (e.g.: ER  $_{>200m}$  [%]). In the round brackets: as in Table 3.

	VarError [ $cm^2$ ]	ER [%]	VAR* [%]	VarError $_{>200m}$ [ $cm^2$ ]	ER $_{>200m}$ [%]	VAR* $_{>200m}$ [%]
OSSE1 (3N)	7.7	-	19	8.5	-	34
OSSE2 (3N+1S)	5.4	30	13	5.6	34	22
OSSE3 (3N+2S)	4.7	39	12	4.7	45	19
OSSE4 (3N+2S+LE)	4.2	46	10	4	53	16

**Table 5.** SSH ocean forecast error statistics. Column 1-3: reduction of the variance of error in the ocean forecast (ER<sub>f</sub>), with respect to OSSE1 (3N) at the 1st, 3rd, and 5th day of forecast. Columns 4-6: as in Columns 1-3, but excluding the shelf areas shallower than 200 m (e.g. 1st $_{>200m}$ ). The legend of the OSSEs is as in Figure 4. Statistics obtained considering the period February-December 2009. Values expressed as a percentage [%].

	ER <sub>f</sub> 1st	ER <sub>f</sub> 3rd	ER <sub>f</sub> 5th	ER <sub>f</sub> 1st $_{>200m}$	ER <sub>f</sub> 3rd $_{>200m}$	ER <sub>f</sub> 5th $_{>200m}$
OSSE2 (3N+1S)	29	25	21	34	28	24
OSSE3 (3N+2S)	39	33	28	45	37	31
OSSE4 (3N+2S+LE)	45	37	31	52	42	35

**Table 6.** Spectral analysis. Columns 2-4: error reduction (%) with respect to OSSE0 (control simulation) at different spatial scales. Columns 5-7: spectral coherence (0.8-0.4) in the OSSEs; the values show the spatial scale (expressed as kilometres) at which the coherence falls below 0.8, 0.6, 0.4.

	ER <sub>spec</sub> [%]			C <sub>spec</sub>		
	200-400 km	100-200 km	50-100 km	0.8	0.6	0.4
OSSE1 (3N)	79	64	10	280 km	155 km	125 km
OSSE2 (3N+1S)	89	79	28	170	125	105
OSSE3 (3N+2S)	89	81	30	165	120	95
OSSE4 (3N+2S+LE)	91	84	38	150	115	90

**Table 7.** Zonal (U) and meridional (V) currents error reduction (ER), with respect to nadir altimeters only (OSSE1). Columns ~~1-3~~: ocean current magnitude ( $m s^{-1}$ ) averaged at the surface ( $M_s$ ), ~~3-4~~100m ( $M_{100m}$ ) and 300m ( $M_{300m}$ ). Columns ~~4, 6-7~~: error reduction in the ocean analysis considering the zonal currents at surface ( $U_s$ ), at 100m ( $U_{100m}$ ) and at 300m ( $U_{300m}$ ). Column ~~25~~: as in Column ~~14~~ but excluding the shelves areas shallower than 200 m ( $U_{s>200m}$ ). Columns ~~58, 7-8~~10-11: as in Columns ~~1-3~~ ~~4,6-7~~ but considering meridional currents. Columns ~~69~~: as in Column ~~2-5~~, but considering meridional currents ( $V_{s>200m}$ ). Values expressed as a percentage [%].~~In the round brackets: as in Table 3.~~

	<u><math>M_s</math></u>	<u><math>M_{100m}</math></u>	<u><math>M_{300m}</math></u>	<b>ER</b> $U_s$	<b>ER</b> $U_{s>200m}$	<b>ER</b> $U_{100m}$	<b>ER</b> $U_{300m}$	<b>ER</b> $V_s$	<b>ER</b> $V_{s>200m}$	<b>ER</b> $V_{100m}$
<b>OSSE2</b> ( <del>3N+1S</del> )	<u>0.12</u>	<u>0.1</u>	<u>0.1</u>	21	23	23	23	23	25	24
<b>OSSE3</b> ( <del>3N+2S</del> )	<u>0.11</u>	<u>0.1</u>	<u>0.1</u>	28	30	29	26	29	31	31
<b>OSSE4</b> ( <del>3N+2S+LE</del> )	<u>0.12</u>	<u>0.1</u>	<u>0.1</u>	35	37	34	30	38	41	36